

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				100% STATE ROADWAY	100% STATE BOX CULVERT	100% STATE BOX CULVERT	100% STATE PIPE CULVERT
				0004 RURAL	0011 PR SN 038-2021	0011 PR SN 038-2020	0011 PR SN 038-2019
50105220	PIPE CULVERT REMOVAL	FOOT	562	562			
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	13380		4600	4520	4260
50800105	REINFORCEMENT BARS	POUND	232670		82270	79630	70770
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1420		700		720
50800515	BAR SPLICERS	EACH	666		230	242	194
51500100	NAME PLATES	EACH	3		1	1	1
54003000	CONCRETE BOX CULVERTS	CU YD	1289.1		462.3	434.1	392.7
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	80.5	80.5			
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	16	16			
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	198	198			
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	148	148			
54213459	END SECTIONS 24"	EACH	5	5			
54213471	END SECTIONS 36"	EACH	4	4			
54245805	INLET BOX, STANDARD 542516	EACH	1	1			

FILE NAME :	USER NAME : duncanbd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pavdot\duncanbd\dms30308\app	5005-shi-500.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO. 4 OF 9 SHEETS	STA.	TO STA.	57	*	ILLINOIS	190	6
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -						*(38-4)RS-2, (38-4)BR, BR1, BR3				
	PLOT DATE = 6/2/2014	DATE -	REVISED -						ILLINOIS FED. AID PROJECT CONTRACT NO. 66757				