

CLASS A PATCHING																			
STATION	NORTHBOUND DRIVING LANE										NORTHBOUND PASSING LANE								REMARKS
	LENGTH	WIDTH	TY II	TY III	TY IV	10" SPEC TY IV	PATCH REINF.	SAW CUTS	TIE BARS	LENGTH	WIDTH	TY II	TY III	TY IV	10" SPEC TY IV	PATCH REINF.	SAW CUTS	TIE BARS	
	FOOT	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	EACH	FOOT	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	EACH	
311+75 - 316+00	425	12				567	567	900.00	212	425	12				567	567	900.00		UNDER SN 038-0130
348+10 - 349+50	140	12			187		187	330.00	70	140	12			187		187	330.00		NEW BOX CULVERT SN 038-2021
351+17	6	12	8.0				8.0	62.00											
374+93	12	12		16.0			16.0	74.00											
393+40	6	12	8.0				8.0	62.00											
397+50	6	12	8.0				8.0	62.00											PATCH OVER NEW CULVERT
398+65 - 399+70	105	12			140		140.0	260.00	52	105	12			140		140	260.00		NEW BOX CULVERT SN 038-2020
506+50 - 507+90	140	12			187		187	330.00	70	140	12			187		187	330.00		NEW BOX CULVERT SN 038-2019
TOTALS			24.0	16.0	514	567	1120	2080.0	404.0			0.0	0.0	514	567	1080	1820.0	0.0	

CLASS A PATCHING																			
STATION	SOUTHBOUND DRIVING LANE										SOUTHBOUND PASSING LANE								REMARKS
	LENGTH	WIDTH	TY II	TY III	TY IV	10" SPEC TY IV	PATCH REINF.	SAW CUTS	TIE BARS	LENGTH	WIDTH	TY II	TY III	TY IV	10" SPEC TY IV	PATCH REINF.	SAW CUTS	TIE BARS	
	FOOT	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	EACH	FOOT	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	EACH	
286+85										6	12	8.0				8.0	62.00		
312+50 - 315+50	300	12				400	400	650.00	150	300	12				400	400	650.00		UNDER SN 038-0130
347+60 - 349+00	140	12			187		187	330.00	70	140	12			187		187	330.00		NEW BOX CULVERT SN 038-2021
373+87	6	12	8.0				8.0	62.00											
374+93	18	12		24.0			24.0	86.00											
390+77	6	12	8.0				8.0	62.00											
396+65	6	12	8.0				8.0	62.00											
397+10	6	12	8.0				8.0	62.00											
398+75 - 399+80	105	12			140		140.0	260.00	52	105	12			140		140	260.00		NEW BOX CULVERT SN 038-2020
401+33	6	12	8.0				8.0	62.00											
424+85 - 426+15	130	12				173	173	310.00	65	130	12				173	173	310.00		UNDER SN 038-0131
433+00	6	12	8.0				8.0	62.00											
434+06	6	12	8.0				8.0	62.00											
507+15 - 508+50	135	12			180		180	320.00	67	135	12			180		180	320.00		NEW BOX CULVERT SN 038-2019
512+20										6	12	8.0				8.0	62.00		
517+50	6	12	8.0				8.0	62.00											
TOTALS			64.0	24.0	507	573	1168	2452.0	404.0			16.0	0.0	507	573	1096	1994.0	0.0	

DRAINAGE SCHEDULE																		
LOCATION	SIDE	CLEANING EXISTING INLETS	INLETS TO BE ADJUSTED (SPECIAL)	PIPE CULVERT REMOVAL	REMOVE INLET BOX	INLETS TY A TY 8 GR	INLET BOX STANDARD 542516	INLET BOX STANDARD 542531	PIPE CULV CLASS A TY 1, 24"	PIPE CULV CLASS D TY 1, 15"	PIPE CULV CLASS D TY 1, 24"	PIPE CULV CLASS D TY 1, 36"	END SECTIONS 24"	END SECTIONS 36"	TRENCH BACKFILL	FLAP GATE 24"	FLAP GATE 36"	STONE RIPRAP CL A3
		EACH	EACH	FOOT	EACH	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT	EACH	EACH	CU YD	EACH	EACH	SQ YD
STA. 287+00	SB	1																
STA. 307+92	MEDIAN			4						4								
STA. 314+70	MEDIAN			12						12								
STA. 347+75	SB			38									1			1		
STA. 348+24	SB			30									1			1		
STA. 348+87	NB			32									1			1		
STA. 349+37	NB			34									1			1		
STA. 397+50	NB						1		80.5						10			
	MEDIAN			190	1			1										
STA. 398+83	NB			39										1				
STA. 398+99	SB			47										1				
STA. 458+90	NB																	19
STA. 480+00	MEDIAN		1															
STA. 506+58	NB			40		1					35					1		
STA. 507+06	NB			30								30						
STA. 507+97	SB			34								34	1			1		
STA. 508+50	SB			32								36		1			1	
STA. 510+00	MEDIAN		1															
TOTALS		1	2	562	1	1	1	1	80.5	16	198	148	5	4	10	6	2	19