

| CODE NO.            | ITEM  | UNIT            | TOTAL QUANTITY | CONSTR. CODE             |
|---------------------|---|-----------------|----------------|--------------------------|
|                     |   |                 |                | ROADWAY<br>0005<br>RURAL |
| 20200600            | EXCAVATING AND GRADING EXISTING SHOULDER        | UNIT            | 458            | 100% STATE               |
| 20400800            | FURNISHED EXCAVATION                            | CU YD           | 22             |                          |
| 40600400            | MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS       | TON             | 21             |                          |
| 40600525            | LEVELING BINDER (HAND METHOD), N50              | TON             | 35             |                          |
| 40600627            | LEVELING BINDER (MACHINE METHOD), 1L-9.5FG, N50 | TON             | 2886           |                          |
| <del>40600895</del> | <del>CONSTRUCTING TEST STRIP</del>              | <del>EACH</del> | <del>1</del>   | <del>1</del>             |
| 40600990            | TEMPORARY RAMP                                  | SO YD           | 156            |                          |
| 40603310            | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50    | TON             | 5771           |                          |
| 40800050            | INCIDENTAL HOT-MIX ASPHALT SURFACING            | TON             | 179            |                          |
| 44000155            | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"         | SO YD           | 1778           |                          |
| 44000158            | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"         | SO YD           | 61054          |                          |
| 48101200            | AGGREGATE SHOULDERS, TYPE B                     | TON             | 5549           |                          |
| 48203021            | HOT-MIX ASPHALT SHOULDERS, 6"                   | SO YD           | 7633           |                          |
| 66700205            | PERMANENT SURVEY MARKERS, TYPE I                | EACH            | 2              |                          |

|             |                    |            |           |   |   |  |  |                    |         |        |              |           |
|-------------|--------------------|------------|-----------|---|---|--|--|--------------------|---------|--------|--------------|-----------|
| FILE NAME * | USER NAME * #USER# | DESIGNED - | REVISED - | STATE OF ILLINOIS<br>DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES   |  |  | F.A.P. RTE.        | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| #FILE#      |                    | DRAWN -    | REVISED - |   |   |  |  | 587                | 122RS-6 | BUREAU | 10           | 3         |
|             |                    | CHECKED -  | REVISED - |   | SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____ |  |  | CONTRACT NO. 66A74 |         |        |              |           |
|             |                    | DATE -     | REVISED - |   | ILLINOIS FED. AID PROJECT   |  |  |                    |         |        |              |           |