

MAINLINE PAVING SCHEDULE

STA. TO STA.	LENGTH	MAINLINE		HMA	HMA SURF	LEV BIND	BIT MAT	MIX JTS	LEV BIND	AGG	TEMP
		WIDTH	AREA	SURF REM	CSE MIX C	(MM) IL-9.5FG	PRIME	CRACKS. & FLANGEWAYS	(HM) IL-9.5FG	WEDGE SHLDS B	RAMP
	FT	FT	SO YD	2 1/4" SO YD	N50 TON	N50 TON	COAT POUND	TON	N50 TON	TON	SO YD
796+06 - 800+83	477	52	2756.0	2756.0	231.50	115.75	1860.30	0.83	1.38	13.58	20.00
800+83 - 850+83	5000	32	17777.8	17777.8	1493.33	746.67	12000.00	5.33	8.89	142.36	
850+83 - 954+04	10322	32	36700.0	36700.0	3082.80	1541.40	24772.49	11.01	18.35	293.89	20.00
954+04 - 955+08	103	SN 006-0086 OMISSION									
955+08 - 1170+68	21560	32	76656.9	76656.9	6439.18	3219.59	51743.40	23.00	38.33	613.86	20.00
1170+68 - 1187+89	1721	46	8796.2	8796.2	738.88	369.44	5937.45	2.64	4.40	45.40	
1187+89 - 1242+06	5417	32	19260.4	19260.4	1617.88	808.94	13000.80	5.78	9.63	154.23	20.00
1242+06 - 1243+40	134	SN 006-0156 OMISSION									
1243+40 - 1266+13	2273	32	8081.8	8081.8	678.87	339.43	5455.20	2.42	4.04	64.72	40.00
1266+13 - 1267+38	125	SN 006-0157 OMISSION									
1267+38 - 1420+00	15262	32	54264.9	54264.9	4558.25	2279.13	36628.80	16.28	27.13	434.54	40.00
ROAD REPAIR SOUTH OF I-80	200	26	577.8	577.8	48.53	24.27	390.00	0.17	0.29		80.00
TOTAL			224871.8	224872	18889	9445	151788	67	112	1763	240

FOLDER 40-3 ILL RTE 40 I-80 TO IL 92				CONTRACT NO. 66C34		
GPS POINT NUMBER OR INDEX NUMBER	DESCRIPTION	EXISTING MONUMENT TYPE	PROPOSED MONUMENT TYPE	BUREAU CO. MONUMENT RECORD TO BE RECORDED	RESPONSIBILITY	
40022	NE COR SEC 9-16-7E	PLUG HOLE	TYPE 1	YES	1	
40029	SW COR SEC 22-17-7E	PK NAIL	TYPE 1	YES	1	
40030	E OTR COR SEC 21-17-7E	SURVEY NAIL	TYPE 1	YES	1	
40031	SE COR SEC 16-17-7E	PK NAIL	TYPE 1	YES	1	
40032	E OTR COR SEC 16-17-7E		TYPE 1	YES	1	
40032A	NE COR OF SE OTR OF NE OTR SEC 16-17-7E IN GRAVEL SHOULDER. ONLY NEEDED IF ADDING ASPHALT SHOULDER	ROD	TYPE 1	YES	1	
40034	W OTR COR SEC 10-17-7E	SURVEY NAIL	TYPE 1	YES	1	
40035	NE COR SEC 9-17-7E		TYPE 1	YES	1	
40039	E OTR COR SEC 33-18-7E		TYPE 1	YES	1	
40039A	NE COR OF SE OTR OF NE OTR SEC 33-18-7E	PK NAIL	TYPE 1	YES	1	
40040	SE COR SEC 28-18-7E	PK NAIL	TYPE 1	YES	1	
40041	E OTR COR SEC 28-18-7E	PK NAIL	TYPE 1	YES	1	
40042	SE COR SEC 21-18-7E	PK NAIL	TYPE 1	YES	1	
40043	E OTR COR SEC 21-18-7E	PK NAIL	TYPE 1	YES	1	
40044	NE COR SEC 21-18-7E	PK NAIL	TYPE 1	YES	1	

THIS NOTE TO BE INCLUDED IN PLANS:
 LISTED MONUMENT LOCATIONS HAVE BEEN RECORDED BY GPS. PRE CONSTRUCTION TIES BY THE R.E. ARE NOT REQUIRED.
 IF AN UNLISTED MONUMENT IS FOUND, IT MUST BE TIED BY THE R.E. AND BROUGHT TO THE ATTENTION OF THE PLATS AND PLANS MANAGER.
 AFTER RESURFACING, THE R.E. IS TO CONTACT THE PLATS AND PLANS MANAGER TO ESTABLISH LOCATIONS FOR PERMANENT SURVEY MARKER CORING.

RESPONSIBILITY:
 1) RESIDENT TO RE-ESTABLISH MONUMENT (PAY ITEM REQUIRED. PERMANENT SURVEY MARKER, TYPE 1)
 2) PLATS AND PLANS TO RE-ESTABLISH MONUMENT

REV. 7/11/14

FILE NAME *	USER NAME * duncnbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE. 646	SECTION (103,104)RS-6	COUNTY BUREAU	TOTAL SHEETS 28	SHEET NO. 8
c:\pwork\p\dot\duncnbd\0304146\0306C34-akt-schedule.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			
		CHECKED -	REVISED -		CONTRACT NO. 66C34								
		DATE -	REVISED -										