

100% STATE

CONSTRUCTION TYPE CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	RDWY 0005 URBAN
25200100	SODDING	SO YD	252	252
20101700	SUPPLEMENTAL WATERING	UNIT	13.2	13.2
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	35	35
40600537	LEVELING BINDER (HAND METHOD), IL-9.5FG, N70	TON	59	59
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70	TON	4941	4941
40600990	TEMPORARY RAMP	SO YD	796	796
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N70	TON	10055	10055
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	401	401
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	6498	6498
42400800	DETECTABLE WARNINGS	SO FT	690	690
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	18283	18283
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	123105	123105
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	963	963
44000600	SIDEWALK REMOVAL	SO FT	6659	6659
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2426	2426
48203100	HOT-MIX ASPHALT SHOULDERS	TON	2048	2048
60260100	INLETS TO BE ADJUSTED	EACH	12	12

17