

MAINLINE												
LOCATION STA. TO STA.	LENGTH	TEMP PVMT MARKING LINE 6"	PREFORMED PLASTIC PVMT MARK - LINE 6"	PVMT MARKING REMOVAL	WORK ZONE PVMT MARKING REMOVAL	MIX FOR CRACKS, JOINTS, & FLANGEWAYS	FIBER MOD. ASPHALT CRACK SEALING	BITUMINOUS MATERIALS (PRIME COAT)	MICRO-SURFACING SINGLE PASS TYPE II MIX D	RAISED REFLECTIVE PVMT MARKER	RAISED REFL PVMT MARKER REMOVAL	
		FT	FT	SQ FT	SQ FT	TON	FT	POUND	SQ YD	EACH	EACH	
NORTHBOUND												
406+64.73	552+08.35	14543.62	3636	3636	1818	1818	1.0	14544	1454	3232	364	364
552+08.35BK	121+28.60AH	STATION EQUATION										
121+28.60	477+82.67 BK	35654.07	8914	8914	4457	4457	2.4	35654	3565	7923	891	891
477+82.67BK	470+23.55AH	STATION EQUATION										
470+23.55AH	561+69.71	9146.16	2287	2287	1144	1144	0.6	9146	915	2032	229	229
561+69.71	562+61.13	OMISSION SN 053-0140										
562+61.13	655+49.51	9288.38	2322	2322	1161	1161	0.6	9288	929	2064	232	232
SOUTHBOUND												
406+64.73	552+08.35	14543.62	3636	3636	1818	1818	1.0	14544	1454	3232	364	364
552+08.35BK	121+28.60AH	STATION EQUATION										
121+28.60	477+82.67 BK	35654.07	8914	8914	4457	4457	2.4	35654	3565	7923	891	891
477+82.67BK	470+23.55AH	STATION EQUATION										
470+23.55AH	561+69.71	9146.16	2287	2287	1144	1144	0.6	9146	915	2032	229	229
561+69.71	562+61.13	OMISSION SN 053-0140										
562+61.13	655+49.51	9288.38	2322	2322	1161	1161	0.6	9288	929	2064	232	232
TOTAL			34318	34318	17160	17160	9.2	137264	13726	30502	3432	3432

FILE NAME =	USER NAME = carpenterdj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pw\work\p\dot\carpenterdj\d037412\0366048-sht-details.dgn	DRAWN -	REVISED -	55			(53-4,4(1),3(1),3,2)I-4	LIVINGSTON	8	6		
PLOT SCALE = 100.0000' / 1".	CHECKED -	REVISED -	CONTRACT NO. 66D48								
PLOT DATE = 5/9/2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT								
						SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____			