

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE ROADWAY
				0005 URBAN
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1	1
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1	1
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1	1
25200110	SODDING, SALT TOLERANT	SO YD	53	53
25200200	SUPPLEMENTAL WATERING	UNIT	1	1
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4
40600537	LEVELING BINDER (HAND METHOD), IL-9.5FG, N70	TON	6	6
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70	TON	505	505
40600990	TEMPORARY RAMP	SO YD	220	220
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1010	1010
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	66	66
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	1296	1296
42400800	DETECTABLE WARNINGS	SO FT	292	292
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	12542	12542

△ SPECIALTY ITEMS

FILE NAME :	USER NAME : duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
or:\pwork\psidot\duncanbd\0377308\038061-ent-500.dgn		DRAWN -	REVISED -		591	(65)RS-1	KENDALL	13	3				
PLOT SCALE : 100.0000 ' / ' IN.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 66061				
PLOT DATE : 6/4/2014		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								