

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				CONT MAINT 100% BRIDGE 0014 027-0010
20200100	EARTH EXCAVATION	CU YD	81	81
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	340	340
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	58	58
44000100	PAVEMENT REMOVAL	SQ YD	101	101
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	840	840
44004250	PAVED SHOULDER REMOVAL	SQ YD	80	80
50102400	CONCRETE REMOVAL	CU YD	57.8	57.8
50157300	PROTECTIVE SHIELD	SQ YD	4	4
50300225	CONCRETE STRUCTURES	CU YD	57.2	57.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	133.6	133.6
50300300	PROTECTIVE COAT	SQ YD	1304	1304
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	39440	39440
50800515	BAR SPLICERS	EACH	128	128
50800530	MECHANICAL SPLICERS	EACH	236	236

FILE NAME =	USER NAME = woodshank-1	DESIGNED - RON WOODSHANK	REVISED -
c:\pwork\pwork\woodshank\1\03080312\	366074-shr-details.dgn	DRAWN - RON WOODSHANK	REVISED -
	PLOT SCALE = 1/8" = 1' / 1/4"	CHECKED - YOGESH PATEL	REVISED -
	PLOT DATE = 5/19/2014	DATE - 2/10/2014	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: \_\_\_\_\_ SHEET NO. 1 OF 4 SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
69T	(27-1HB-2)IR	FORD	27	3
CONTRACT NO. 66074				
ILLINOIS FED. AID PROJECT				

*Rev.*