

100% STATE

SUMMARY OF QUANTITIES					
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0005	0005
				PUTNAM COUNTY	LASALLE COUNTY
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17.5	9.1	8.4
40600990	TEMPORARY RAMP	SQ YD	44	22	22
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	4906	2555	2351
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	58403	30411	27992
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1954	850	1104
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	EACH	1	0.5	0.5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6065	3158	2907
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2022	1053	969
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	103222	49156	54066
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	8703	5252	3451
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	252	131	121
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	252	131	121
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	39423	20528	18895
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5 FG, N50	TON	2453	1277	1176
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	42	21	21
Z0034105	MATERIAL TRANSFER DEVICE	TON	7359	3832	3527

*Specialty Items

FILE NAME :	USER NAME : smsthd	DESIGNED - BDS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
\\pvc-work\pvc\smsthd\0202011\0366179-1ht-deta1.dgn	DRAWN - BDS	CHECKED -	REVISED -					619	103RS-4	LASALLE	6	3
PLOT SCALE = 100,0000 ' / in.	DATE - NOVEMBER 2013	DATE -	REVISED -		SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.			CONTRACT NO. 66E07				
PLOT DATE = 6/6/2014					ILLINOIS FED. AID PROJECT							