EB I - 74 FENCE MM 32 THRU 54							
STA to STA	FENCE REMOVAL (FEET)	WOVEN WIRE FENCE (FEET)	REMARKS				
51+08 to 63+30	10	10	4' woven fence w/stl T pst: also from 56+90 to 57+00 fence torn				
63+30 to 67+87	457	457	4' woven fence w/wdn & stl pst. Each end are wdn pst				
103+97 to 104+42	45	45	4' woven fence w/stl T pst, fence down trees				
110+93 to 112+80	187	187	4' woven fence w/stl T pst trees down on fence in couple locations				
MM 33.9 = Sta 129+30							
Henry County	699	699	Henry / Knox County Line Sta. 129+37				
177+38 to 177+70	85	85	4' woven fence stl T pst tied into bridge				
178+80 to 179+00	49	49	4' woven fence stl T pst tied into bridge				
179+00 to 182+50	350	350	4' woven fence w/ stl T pst				
201+47 to 202+13	66	66	4' woven fence w/stl T pst @ pipe culvert crossing,				
608+90 (US 34) to		24.65	Ramp from EB US 34 to EB 1-74. Tie both ends of proposed fence into				
222+90 (1-74)	1	2165	exiting fence				
224+24 to 224+32	32	32	4' woven fence @ box culvert w/crnr psts w/stl T psts,				
225+50 to 225+80	30	30	Replace wood posts and old fence to tie into existing ROW				
264+52 to 265+02	50	50	4' woven fence w/stl T psts				
333+63 to 334+60	97	97	4' woven fence w/stl T psts				
343+42 to 344+24	82	82	4' woven fence w/stl T psts				
		MM 38 = S	ta 345+20 MM 39 = 395+85				
413+81 to 415+44	163	163	4' woven fence w/stl T psts. Jst N of HENDERSON crk				
416+62 to 418+03	141	141	4' woven fence w/stl T psts, tree line area				
421+45 to 423+65	220	220	4' woven fence w/stl T psts, trees on the down fence,				
439+45 to 439+85	40	40	4' woven fence w/stl T psts				
MM 40 = Sta 448+30							
455+63 to 456+08	45	45	4' woven fence w/stl T psts				
458+40 to 458+85	45	45	4' woven fence w/stl T psts				
484+70 to 484+85	15	15	4' woven fence w/stl T psts				
Knox County	1510	3635					
TOTAL (5)	2209	4334					

	EB I	- 74 FEN	CE MM 32 THRU 54				
STA to STA FENCE REMOVAL (FEET)		WOVEN WIRE FENCE (FEET)	REMARKS				
490+27 to 491+06	79	79	4' woven fence w/stl psts				
493+06 to 494+54 148		148	4' woven fence w/stl T psts				
		MI	M 41 = Sta 503+46				
506+04 to 507+07	+04 to 507+07 103 103 4' woven fence w/stl T psts,						
514+10 to 514+36	26	26	4' woven fence w/stl T psts				
523+60 to 524+00	+00 40 40		4' woven fence w/stl psts				
		STATION EQUA	TION 530 + 12.33 BK = 1+00 AH				
10+39 to 11+00 61 61 4' woven fence w/stl T psts		4' woven fence w/stl T psts					
		M	M 42 = Sta 27+22				
29+47 to 29+65		18	No fence DOUBLE BARREL culvert				
40+80 to 41+20	40	40	4' woven fence w/stl T psts, low fence				
47+24 to 48+24	100	100	4' woven fence w/stl T psts, low fence				
60+35 to 61+07	72	72	4' woven fence w/stl T psts				
63+45 to 64+13	68	68	4' woven fence w/stl T psts				
		M	M 43 = Sta 80+00				
103+00 to 103+25	25	25	4' woven fence w/stl T psts				
105+75 to 106+05	30	30	4' woven fence w/stl T psts				
144+58 to 146+65	207	207	4' woven fence w/stl T psts				
181+40 to 181+90	50	50	4' woven fence w/stl T psts				
		MI	M 45 = Sta 185+63				
		STA EQUATION E	NGLISH 195+27 = METRIC 72+700				
74+825 to 74+831	58	58	4' woven fence w/stl T psts				
74+831 to 74+855	79	79	4' woven fence w/stl T psts				
74+855 to 74+859	30	30	4' woven fence w/stl T psts				
74+859 to 74+873	46	46 4' woven fence w/stl T psts					
		MI	M 47 = Sta 75+630				
76+088 to 76+116	92	92	4' woven fence down				
TOTAL (6)	1354	1372					

	FILE NAME =	USER NAME = AUBREYGS	DESIGNED -	REVISED	
	D468B97-topo.dgn		DRAWN	REVISED	
		PLOT SCALE = 40.0000 '/ in.	CHECKED	REVISED	
	Default	PLOT DATE = 5/22/2014	DATE	REVISED	

		F.A.I. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEE NO.
SCHEDULE OF QUANTITIES			48-[(24,25)-;(26-1,26,27	7)[-2]	HENRY/KNOX	7	6
					CONTRACT	NO. 6	58B97
	SCALE: SHEET OF SHEETS STA TO STA		ILLINOIS F	ED. AID	PROJECT		