

SCHEDULE OF HMA WIDENING QUANTITIES (CONTINUED)											
				OMISSION NOTES	LENGTH	AREA	AGGREGATE WEDGE SHOULDER, TY B	HMA BASE CSE WIDENING, 9"	PAVEMENT REMOVAL (SPECIAL)	POLYMERIZED BIT. MAT. (PRIME COAT)	
											FEET
<b>HENDERSON COUNTY (CONTINUED)</b>											
RT.	STA.	224+80.69	TO	230+18.15		537.46	179.15	7.66	179.15	179.15	0.04
RT.	STA.	230+18.15	TO	230+22.15	4'X6' BOX						
RT.	STA.	230+22.15	TO	243+78.87		1,356.72	452.24	19.33	452.24	452.24	0.10
RT.	STA.	243+78.87	TO	243+80.87	2'X2' BOX						
RT.	STA.	243+80.87	TO	286+02.23		4,221.36	1,407.12	60.15	1,407.12	1,407.12	0.31
RT.	STA.	286+02.23	TO	286+39.16	850 N						
RT.	STA.	286+39.16	TO	308+40.16		2,201.00	733.67	31.36	733.67	733.67	0.16
RT.	STA.	308+40.16	TO	308+43.16	3'X3' BOX						
RT.	STA.	308+43.16	TO	319+80.36		1,137.20	379.07	16.21	379.07	379.07	0.08
RT.	STA.	319+80.36	TO	319+82.36	24" PIPE						
RT.	STA.	319+82.36	TO	334+98.44		1,516.08	505.36	21.60	505.36	505.36	0.11
RT.	STA.	334+98.44	TO	334+99.94	18" PIPE						
RT.	STA.	334+99.94	TO	339+06.83		406.89	135.63	5.80	135.63	135.63	0.03
RT.	STA.	339+06.83	TO	339+61.91	750 N						
RT.	STA.	339+61.91	TO	358+64.63		1,902.72	634.24	27.11	634.24	634.24	0.14
RT.	STA.	358+64.63	TO	370+00.00	WYE						
RT.	STA.	370+00.00	TO	390+12.11		2,012.11	670.70	28.67	670.70	670.70	0.15
RT.	STA.	390+12.11	TO	390+14.11	2'X2' BOX						
RT.	STA.	390+14.11	TO	416+01.51		2,587.40	862.47	36.87	862.47	862.47	0.19
RT.	STA.	416+01.51	TO	416+54.89	2000 E						
RT.	STA.	416+54.89	TO	455+39.74		3,884.85	1,294.95	55.36	1,294.95	1,294.95	0.28
RT.	STA.	455+39.74	TO	469+79.52	GUTTER						
<b>SUB-TOTAL:</b>								<b>310.13</b>	<b>7,254.60</b>	<b>7,254.60</b>	<b>1.60</b>
<b>HENDERSON COUNTY TOTAL:</b>								<b>616</b>	<b>14,413</b>	<b>14,413</b>	<b>3</b>

FILE NAME =	USER NAME = aubreygs	DESIGNED -	REVISED -
68C07 - IL 116 Henderson and Warren.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/21/2014	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULES OF QUANTITIES**

NOT TO SCALE    SHEET 2    OF 5    SHEETS    STA.    TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
665	137W-1+ (138, 139)W-2	HENDERSON/ WARREN	15	7
CONTRACT NO. 68C07				
ILLINOIS FED. AID PROJECT				