

MAINLINE IMPROVEMENTS										
BITUMINOUS MATERIAL (PRIME COAT) RATE - 0.00038 T/SY				40600275	40603340	44000157	78100100	78300200		
AGGREGATE (PRIME COAT) RATE - 0.002 T/SY				BITUMINOUS	HMA SURFACE	HMA SURFACE	RAISED REFL.	RAISED REFL.		
BITUMINOUS SURFACE / BINDER (112 LBS) RATE - 0.056 T/SY+IN				MATERIALS	COURSE	REMOVAL,	PAVEMENT	PAVEMENT		
				(PRIME COAT)	MIX "D", N 70	2"	MARKER	MARKER		
					d=2"			REMOVAL		
LOCATION		LENGTH	WIDTH	AREA	LB	TON	SQ YD	EACH	EACH	
STATION TO STATION		FT	FT	SQ YD						
STA. 118+88.57 TO STA. 127+50.00		WBPL, WBDL	861.43	24.00	2,297.15	1033.72	287.15	2,297.15	19	19
STA. 118+88.57 TO STA. 127+50.00		EBTL	861.43	12.00	1,148.57	516.86	143.57	1,148.57	8	8
TOTAL:					1550.57	430.72	3,445.72	27	27	
USE:					1551	431	3446	27	27	

40600990			
TEMPORARY RAMP (SQ YD)			
LOCATION	LENGTH	WIDTH	AREA
STATION TO STATION - LT/RT	FT	FT	SQ YD
STA. 118+88.57 LT	6.7	24.0	17.8
STA. 118+88.58 RT	6.7	12.0	8.9
STA. 127+50.0 LT	6.7	24.0	17.9
STA. 127+50.0 RT	6.7	12.0	8.9
TOTAL:			140.3
USE:			140

78006120					
PERFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 5" (FOOT)					
LOCATION		LENGTH	COLOR	CENTERLINE	EDGE LINE
STATION TO STATION		FT	YELLOW/ WHITE	SKIP-DASH FT	SOLID FT
STA. 118+88.57 TO STA. 124+49.39	LT CL	560.82	YELLOW	140.21	
STA. 126+00.00 TO STA. 127+50.0	LT CL	150.00	YELLOW	37.50	
STA. 118+88.57 TO STA. 118+42.16	RT CL	46.41	YELLOW	11.60	
STA. 118+88.57 TO STA. 127+50.0	LT DL	861.43	WHITE		861.43
STA. 118+88.57 TO STA. 124+41.72	LT PL	553.15	YELLOW		553.15
STA. 126+00.00 TO STA. 127+50.0	LT PL	150.00	YELLOW		150.00
STA. 118+88.57 TO STA. 124+76.91	RT TL	588.34	YELLOW		588.34
STA. 122+95.57 TO STA. 125+08.5	RT TL	212.95	WHITE		212.95
STA. 125+41.63 TO STA. 127+50.0	RT TL	208.37	WHITE		208.37
STA. 125+90.00 TO STA. 127+50.0	RT TL	160.00	YELLOW		160.00
SUB TOTAL:				189.31	2,734.24
TOTAL:				2,923.55	
USE:				2,924	

LOCATION		LENGTH	70300100	70301000
STATION TO STATION		FT	SHORT TERM PAV'T MARK	WORK ZONE PAV'T MARK REM w=4"
			FOOT	SQ FT
STA. 118+88.57 TO STA. 124+49.3	LT CL	560.82	56.08	18.69
STA. 126+00.00 TO STA. 127+50.0	LT CL	150.00	15.00	5.00
STA. 118+88.57 TO STA. 118+42.16	RT CL	46.41	4.64	1.55
STA. 118+88.57 TO STA. 127+50.0	LT DL	861.43	86.14	28.71
STA. 118+88.57 TO STA. 124+41.7	LT PL	553.15	55.32	18.44
STA. 126+00.00 TO STA. 127+50.0	LT PL	150.00	15.00	5.00
STA. 118+88.57 TO STA. 124+76.9	RT TL	588.34	58.83	19.61
STA. 122+95.57 TO STA. 125+08.5	RT TL	212.95	21.30	7.10
STA. 125+41.63 TO STA. 127+50.0	RT TL	208.37	20.84	6.95
STA. 125+90.00 TO STA. 127+50.0	RT TL	160.00	16.00	5.33
TOTAL:			349.15	116.38
USE:			349	116

78006180			
PERFORMED THERMOPLASTIC PAVEMENT MARKING LINE 24" (FOOT)			
LOCATION	TYPE	LENGTH	
STATION (L/T/RT)		WHITE FT	
STA. 124+76.91	RT	STOP BAR	12.00
STA. 126+00.00	RT	STOP BAR	24.00
TOTAL:		36.00	
USE:		36	

△ REVISED 7-21-14