

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE BRIDGE 0014 S.N. 075-0159
67100100	MOBILIZATION	L SUM	1	1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	3	3
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4
X0326899	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	2	2
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	10	10
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	28	28
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	40	40

10

FILE NAME *	USER NAME * dudleybm	DESIGNED - DMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITY				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D:\OPERATIONS\Bridgplans\CAD\72083 - 58	0758159 Patching 2814\72083.dgn	DRAWN - DMS	REVISED -						566	(17) I	PIKE	12	3
Default	PLOT SCALE * 48.0000 ' / in.	CHECKED -	REVISED -		CONTRACT NO. 72083								
	PLOT DATE * May-16-2014 10:01:11AM	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		