

				100% STATE							100% STATE		
				FAP 774	FAS 2801	FAP 774					FAP 774	FAS 2801	FAP 774
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	EFF. CO. 0005	FAYETTE CO. 0005	EFF. CO. 0021	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	EFF. CO. 0005	FAYETTE CO. 0005	EFF. CO. 0021
20200100	EARTH EXCAVATION	CU YD	7451	7451			30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	3699	3699		
20800150	TRENCH BACKFILL	CU YD	9.7	9.7			30201500	LIME	TON	93	93		
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1009	1009			35101400	AGGREGATE BASE COURSE, TYPE B	TON	155	155		
25000200	SEEDING, CLASS 2	ACRE	3.1	3.1			35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	699	699		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	280	280			35501330	HOT-MIX ASPHALT BASE COURSE, 11 1/2"	SQ YD	3224	3224		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	280	280			40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	220	204	16	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	280	280			40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	7229	6308	921	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	6	6			40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	970	840	130	
25100115	MULCH, METHOD 2	ACRE	3.1	3.1			40600990	TEMPORARY RAMP	SQ YD	269	247	22	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	930	930			40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "2", N70	TON	14493	12759	1734	
28000305	TEMPORARY DITCH CHECKS	FOOT	440	440			40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	1465	1465		
28000400	PERIMETER EROSION BARRIER	FOOT	250	250			40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	257	242	15	
28000500	INLET AND PIPE PROTECTION	EACH	11	11			44000100	PAVEMENT REMOVAL	SQ YD	509	509		
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	120	120									