

SUMMARY OF QUANTITIES				100% STATE		
				FAP 774	FAS 2801	FAP 774
				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	EFF. CO. 0005	FAYETTE CO. 0005	EFF. CO. 0021
60500060	REMOVING INLETS	EACH	1	1		
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	5	5		
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	21	21		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	611	611		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	129	129		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	21	21		
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	218	218		
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1		
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12		
67100100	MOBILIZATION	L SUM	1	1		
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1	1		

SUMMARY OF QUANTITIES				100% STATE		
				FAP 774	FAS 2801	FAP 774
				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	EFF. CO. 0005	FAYETTE CO. 0005	EFF. CO. 0021
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.9	0.1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.9	0.1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 2.1	L SUM	1	1		
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 2.2	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	9	9		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19608	17451	2157	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	177852	158288	19564	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2179	1939	240	

* SPECIALTY ITEM

FILE NAME =	USER NAME = staffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\staffennk\d0121426\07	4092-shr-a0q.dgn	DRAWN -	REVISED -		2801	102RS-3,103RS-2,102N		84	5		
	PLOT SCALE = 1/8" = 1' / in.	CHECKED -	REVISED -		Effingham, Fayette		CONTRACT NO. 74052				
	PLOT DATE = 6/6/2014	DATE -	REVISED -		SCALE: NA	SHEET 3 OF 5 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT			