

				100% STATE							100% STATE		
				FAP 774	FAS 2801	FAP 774					FAP 774	FAS 2801	FAP 774
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	EFF. CO. 0005	FAYETTE CO. 0005	EFF. CO. 0021	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	EFF. CO. 0005	FAYETTE CO. 0005	EFF. CO. 0021
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	124.8	124.8			* 81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	455			455
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13887	13887			* 83600355	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	4			4
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	510	510			* 83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	16			16
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	297	297			* 84200804	REMOVAL OF POLE FOUNDATION	EACH	4			4
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	565	565			* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	4			4
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	108	108			* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1			1
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	177852	158288	19564		* X0325924	CLEAN, RELAMP AND MAINTENANCE OF EXISTING LUMINAIRE	EACH	4			4
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1053	893	160		X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4	4		
* 78200300	PRISMATIC CURB REFLECTOR	EACH	20	20			X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	5	5		
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1		X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	3	3		
* 81028550	UNDERGROUND CONDUIT, INTERMEDIATE METAL, 2" DIA.	FOOT	175			175	X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	115530	100730	14800	
* 81028750	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA.	FOOT	175			175	X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	507	507		

* SPECIALTY ITEM