

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH FOOT	PAINT PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 4"	SHORT-TERM PAVEMENT MARKING FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	RAISED REFLECTIVE PAVEMENT MARKER (TWO-WAY AMBER) EACH	RAISED REFLECTIVE PAVEMENT MARKER (ONE-WAY CRYSTAL) EACH
733+89.00 TO 756+46.00	2257.0	5078.3	5078.3	672	74.7	29	0
757+05.30 TO 799+00.00	4194.7	9438.1	9438.1	1260	140.0	53	0
799+00.00 TO 810+67.20	1167.2	2626.2	2626.2	348	38.7	30	60
811+74.90 TO 813+00.00	125.1	281.5	281.6	36	4.0	4	8
813+00.00 TO 860+15.00	4715.0	10608.8	10608.8	1416	157.3	60	0
881+94.00 TO 973+70.50	9176.5	35308.1	35308.1	2748	305.3	115	0
973+70.50 TO 975+61.50	191.0	849.8	849.8	0	0.0	0	0
975+61.50 TO 1040+68.50	6507.0	18416.8	18416.8	1956	217.3	81	0
1040+68.50 TO 1041+71.50	103.0	658.8	658.8	0	0.0	0	0
1041+71.50 TO 1087+61.50	4590.0	14693.5	14693.5	1380	153.3	57	0
1087+61.00 TO 1088+59.00	98.0	595.5	595.5	0	0.0	0	0
1088+59.00 TO 1391+84.00	30325.0	70236.3	70236.3	9096	1010.7	379	0
1391+84.00 TO 1393+61.00	177.0	819.3	819.3	0	0.0	0	0
1393+61.00 TO 1416+88.90	2327.9	8241.8	8241.8	696	77.3	29	0
TOTALS		177853.0	177853.0	19608	2179.0	837	68

NOTE: SEE NEXT SHEET FOR THERMOPLASTIC