

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FEDERAL 10% STATE 0005		
40603092	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N90	TON	4505	4505		
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	3544	3544		
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	3293	3293		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	17888	17888		
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SO YD	427	427		
44000175	HOT-MIX ASPHALT SURFACE REMOVAL, 6 1/2"	SO YD	15582	15582		
44000184	HOT-MIX ASPHALT SURFACE REMOVAL, 8 1/2"	SO YD	10822	10822		
44004250	PAVED SHOULDER REMOVAL	SO YD	1431	1431		
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SO YD	8	8		
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SO YD	188	188		
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SO YD	145	145		
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SO YD	163	163		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FEDERAL 10% STATE 0005		
44213000	PATCHING REINFORCEMENT	SO YD	504	504		
44213200	SAW CUTS	FOOT	2594	2594		
44213204	TIE BARS 3/4"	EACH	134	134		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	3125	3125		
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	20124	20124		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	9040	9040		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20124	20124		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2520	2520		

FILE NAME =	USER NAME = steffennk	DESIGNED -	REVISED -
c:\pwork\pudat\steffennk\08093168\07	*336-4ht-400.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 1/1m	CHECKED -	REVISED -
Default	PLOT DATE = 8/9/2014	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	118-451RS-4	CUMBERLAND	17	3
			CONTRACT NO. 74386	
ILLINOIS FED. AID PROJECT				