

RESURFACING SCHEDULE

STATION TO STATION	LENGTH FOOT	HOT-MIX ASPHALT SURFACE REMOVAL, 2" SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4" SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 6 1/2" SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 8 1/2" SQ YD	BITUMINOUS MATERIALS (PRIME COAT) POUND	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N90 TON	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90 TON	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80 TON	MATERIAL TRANSFER DEVICE TON	SHOULDER RUMBLE STRIPS, 16 INCH FOOT
WB I-70											
2771+40.00 TO 2772+59.71	119.7	212.8	0.0	319.2	0.0	383.1	40.2	40.2	41.5	121.9	239.4
2772+59.71 (BK) = 9+02.89 (AH)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
9+02.89 TO 9+41.60	38.7	68.8	0.0	103.2	0.0	123.9	13.0	13.0	13.4	39.4	77.4
9+41.60 TO 50+00.00	4058.4	7214.9	0.0	0.0	10822.4	12986.9	2575.7	1363.6	1406.9	5346.2	8116.8
50+00.00 TO 89+55.20	3955.2	7031.5	0.0	10547.2	0.0	12656.6	1328.9	1328.9	1371.1	4028.9	7910.4
89+55.20 TO 90+55.20	100.0	177.8	0.0	266.7	0.0	320.0	16.8	16.8	45.5	79.1	200.0
90+55.20 TO 92+15.20	160.0	284.4	426.7	0.0	0.0	320.0	0.0	0.0	90.1	90.1	320.0
92+15.20 TO 93+15.20	100.0	177.8	0.0	266.7	0.0	320.0	16.8	16.8	45.5	79.1	200.0
93+15.20 TO 108+45.00	1529.8	2719.6	0.0	4079.5	0.0	4895.4	514.0	514.0	530.3	1558.3	3059.6
TOTALS		17888.0	427.0	15582.0	10822.0	32006.0	4505.0	3293.0	3544.0	11343.0	20124.0

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\p\dot\steffenmk\d0393168\07	74386-sh1-sch.dgn	DRAWN -	REVISED -						70	(18-45)RS-4	CUMBERLAND	17	9
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -		SCALE: N/A				SHEET 1 OF 2 SHEETS		STA.	TO STA.	CONTRACT NO. 74386
	PLOT DATE = 5/9/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								