

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	MODIFIED URETHANE PAVEMENT MARKING - LINE 4" WHITE	MODIFIED URETHANE PAVEMENT MARKING - LINE 4" YELLOW	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID-LINE-6" WHITE	GROOVING FOR RECESSED PAVEMENT MARKING 5"	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	EACH
WB I-70											
2771+40.00 TO 2772+59.71	119.7	119.7	119.7	30.0	239.4	239.4	30.0	100.0	6.7	94.8	2.0
2772+59.71 (BK) = 9+02.89 (AH)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
9+02.89 TO 108+45.00	9942.1	9942.1	9942.1	2490.0	19884.2	19884.2	2490.0	8940.0	596.0	7873.1	248.0
TOTALS		10062.0	10062.0	2520.0	20124.0	20124.0	2520.0	9040.0	603.0	7968.0	250.0

PATCHING SCHEDULE

	CLASS A PATCHES, TYPE I, 8 INCH	CLASS A PATCHES, TYPE II, 8 INCH	CLASS A PATCHES, TYPE III, 8 INCH	CLASS A PATCHES, TYPE IV, 8 INCH	PATCHING REINFORCEMENT	SAW CUTS	TIE BARS 3/4"	PAVED SHOULDER REMOVAL	HOT-MIX ASPHALT SHOULDERS
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	EACH	SQ YD	TON
TOTALS	8.0	188.0	145.0	163.0	504.0	2594.0	134.0	1431.0	1122.0