

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	100% STATE CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		FAYETTE COUNTY 0004	EFFINGHAM COUNTY 0004	FAYETTE S.N. 026-0055 0014
35501303	HOT-MIX ASPHALT BASE COURSE, 4 3/4"	SO YD	50046	42209	7837	
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SO YD	261			261
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	460	460		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	2311	1733	578	
40600990	TEMPORARY RAMP	SO YD	994	861	133	
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	89701	54985	34716	
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	29713	18285	11428	
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	31979	19597	12382	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	730	730		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	95			95
44000100	PAVEMENT REMOVAL	SO YD	26331	18363	7836	132
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	3161	3161		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	4383	3820	563	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	100% STATE CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		FAYETTE COUNTY 0004	EFFINGHAM COUNTY 0004	FAYETTE S.N. 026-0055 0014
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SO YD	4355	1653	2702	
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SO YD	2178	2178		
44000173	HOT-MIX ASPHALT SURFACE REMOVAL, 6"	SO YD	200480	121107	79373	
44004250	PAVED SHOULDER REMOVAL	SO YD	75789	45839	29950	
44200620	CLASS A PATCHES, TYPE II, 14 INCH	SO YD	43	43		
44201043	CLASS B PATCHES, TYPE II, 16 INCH	SO YD	1289	561	728	
44201047	CLASS B PATCHES, TYPE III, 16 INCH	SO YD	108	40	68	
44201048	CLASS B PATCHES, TYPE IV, 16 INCH	SO YD	113	60	53	
44201299	DOWEL BARS 1 1/2"	EACH	2920	1300	1620	
44213000	PATCHING REINFORCEMENT	SO YD	264	143	121	
44213200	SAW CUTS	FOOT	7826	3636	4190	
44213208	TIE BARS 1 1/4"	EACH	60	35	25	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	21993	13238	8755	
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SO YD	94736	57299	37437	

FILE NAME =	USER NAME = swarter	DESIGNED -	REVISED -
o:\pwork\p\dots\swarter\d0186577\077469-shs'aoq.dgn		DRAWN -	REVISED -
PLOT SCALE = 1/8"=1'-0"		CHECKED -	REVISED -
PLOT DATE = 8/5/2014		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCALE: NA		SHEET NO. 1 OF 5 SHEETS		STA.	TO STA.
-----------	--	-------------------------	--	------	---------

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TO	(26-5.26-5-1.25-1-1R)		92	4
CONTRACT NO. 74469				
ILLINOISIFIED AID PROJECT				

• EFFINGHAM & FAYETTE