SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE CONSTRUCTION TYPE CODE: FAYETTE COUNTY 0004	EFFINGHAM COUNTY 0004	FAYETTE S.N. 026-0055 0014
48203100	HOT-MIX ASPHALT SHOULDERS	TON	27274	16746	10528	
50102400	CONCRETE REMOVAL	CU YD	39.6			39.6
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1			1
50157300	PROTECTIVE SHIELD	SQ YD	538			538
50200100	STRUCTURE EXCAVATION	CU YD	221			221
50300225	CONCRETE STRUCTURES	CU YD	62.4	9.2		53.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	419.2			419.2
50300260	BRIDGE DECK GROOVING	SQ YD	968			968
50300300	PROTECTIVE COAT	SQ YD	1282			1282
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2597			2597
50500505	STUD SHEAR CONNECTORS	EACH	3324			3324
50800105	REINFORCEMENT BARS	POUND	15343	9505	5838	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	95070	670		94400
50800515	BAR SPLICERS	EACH	916			916

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE CONSTRUCTION TYPE CODE: FAYETTE COUNTY 0004	EFFINGHAM COUNTY 0004	FAYETTE S.N. 026-0055 0014
50900200	STEEL RAILING, TYPE 2399	FOOT	1844	920	924	
51100100	SLOPE WALL 4 INCH	SQ YD	249	177		72
51500100	NAME PLATES	EACH	2			2
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12			12
52100520	ANCHOR BOLTS, 1"	EACH	24			24
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	98			98
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4			4
60100074	SHOULDER REMOVAL AND REPLACEMENT 8"	FOOT	169212	102805	66407	
60100905	PIPE DRAINS 4"	FOOT	80			80
60107700	PIPE UNDERDRAINS 6"	FOOT	166198	100939	65259	
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	9603	5991	3612	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	7987.5	5187.5	2700	100
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	13	6	3	4

* SPECIALTY ITEM

* EFFINGHAM & FAYETTE

FILE NAME = c:\pw_work\pwidot\swartzrw\d0186577\D077469-sht-sog.dgn	USER NAME = swartzrw	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 122.2000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 6/5/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA | SHEET NO. 2 OF 5 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	126-5,26-5-1,26-1-1JR	*	92	5

CONTRACT NO. 74469

ILLINOIS FED. AID PROJECT