

RESURFACING SCHEDULE (CONTINUED)

| STATION TO STATION | LENGTH FOOT | HOT-MIX ASPHALT SHOULDERS, 13" SQ YD | RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT SQ YD | TRIAXIAL GEOGRID REINFORCEMENT, TYPE I SQ YD | SUBBASE GRANULAR MATERIAL (SPECIAL) CU YD | BITUMINOUS MATERIALS (PRIME COAT) POUND | HOT-MIX ASPHALT BASE COURSE, 4 3/4" SQ YD | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90 TON | POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N105 TON | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80 TON | LEVELING BINDER (MACHINE METHOD), N90 TON | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 TON | HOT-MIX ASPHALT SHOULDERS TON | AGGREGATE WEDGE SHOULDER, TYPE B TON | SHOULDER RUMBLE STRIPS, 16 INCH FOOT | TEMPORARY RAMP SQ YD | MATERIAL TRANSFER DEVICE TON |
|--------------------------|----------------|---|--|--|---|---|---|---|---|--|---|--|----------------------------------|--|---|-------------------------|---------------------------------|
| WB I-70 | | | | | | | | | | | | | | | | | |
| 1043+44.00 TO 1045+19.00 | 175.0 | 194.4 | 0.0 | 0.0 | 0.0 | 735.0 | 0.0 | 8.5 | | 60.7 | 0.0 | 0.0 | 46.3 | 50.4 | 350.0 | 66.7 | 81.4 |
| 1045+19.00 TO 1056+15.00 | 1096.0 | 1217.8 | 2922.7 | 0.0 | 0.0 | 3945.6 | 0.0 | 1170.2 | 411.4 | 379.9 | 0.0 | 0.0 | 390.3 | 315.5 | 2192.0 | 0.0 | 791.3 |
| 1056+15.00 TO 1057+15.00 | 100.0 | 111.1 | 0.0 | 0.0 | 0.0 | 420.0 | 0.0 | 106.8 | 37.5 | 34.7 | 0.0 | 0.0 | 33.0 | 28.8 | 200.0 | 0.0 | 72.2 |
| 1057+15.00 TO 1068+45.00 | 1130.0 | 1255.6 | 3013.3 | 0.0 | 0.0 | 4068.0 | 0.0 | 1206.5 | 424.2 | 391.7 | 0.0 | 0.0 | 372.6 | 325.3 | 2260.0 | 0.0 | 815.9 |
| 1068+45.00 TO 1078+50.00 | 1005.0 | 1116.7 | 0.0 | 2680.0 | 1191.1 | 3819.0 | 2680.0 | 1050.6 | 375.2 | 348.4 | 0.0 | 0.0 | 200.1 | 38.2 | 2010.0 | 0.0 | 723.6 |
| 1078+50.00 TO 1086+30.00 | 780.0 | 866.7 | 2080.0 | 0.0 | 0.0 | 2808.0 | 0.0 | 832.8 | 292.8 | 270.4 | 0.0 | 0.0 | 257.2 | 224.6 | 1560.0 | 0.0 | 563.2 |
| 1086+30.00 TO 1087+30.00 | 100.0 | 111.1 | 0.0 | 0.0 | 0.0 | 420.0 | 0.0 | 106.8 | 37.5 | 34.7 | 0.0 | 0.0 | 33.0 | 28.8 | 200.0 | 0.0 | 72.2 |
| 1087+30.00 TO 1100+95.00 | 1365.0 | 1516.7 | 3640.0 | 0.0 | 0.0 | 4914.0 | 0.0 | 1457.4 | 512.4 | 473.2 | 0.0 | 0.0 | 450.1 | 393.0 | 2730.0 | 0.0 | 985.6 |
| 1100+95.00 TO 1101+95.00 | 100.0 | 111.1 | 0.0 | 0.0 | 0.0 | 420.0 | 0.0 | 106.8 | 37.5 | 34.7 | 0.0 | 0.0 | 33.0 | 28.8 | 200.0 | 0.0 | 72.2 |
| 1101+95.00 TO 1124+81.00 | 2286.0 | 2540.0 | 6096.0 | 0.0 | 0.0 | 8229.6 | 0.0 | 2440.8 | 858.1 | 792.5 | 0.0 | 0.0 | 753.9 | 658.1 | 4572.0 | 0.0 | 1650.6 |
| 1124+81.00 TO 1132+50.00 | 769.0 | 854.4 | 2050.7 | 0.0 | 0.0 | 3436.9 | 0.0 | 1112.2 | 392.6 | 363.1 | 0.0 | 0.0 | 253.6 | 221.4 | 769.0 | 0.0 | 755.7 |
| 1132+50.00 TO 1133+50.00 | 100.0 | 111.1 | 0.0 | 0.0 | 0.0 | 637.3 | 0.0 | 182.5 | 64.6 | 59.8 | 0.0 | 0.0 | 33.0 | 28.8 | 100.0 | 0.0 | 124.4 |
| 1133+50.00 TO 1135+62.00 | 212.0 | 235.6 | 565.3 | 0.0 | 0.0 | 878.5 | 0.0 | 276.6 | 97.5 | 90.1 | 0.0 | 0.0 | 69.9 | 61.0 | 212.0 | 0.0 | 187.6 |
| 1135+62.00 TO 1139+25.00 | 363.0 | 403.3 | 968.0 | 0.0 | 0.0 | 1306.8 | 0.0 | 387.6 | 136.3 | 125.8 | 0.0 | 0.0 | 119.7 | 104.5 | 726.0 | 0.0 | 262.1 |
| 1139+25.00 TO 1149+05.00 | 980.0 | 1088.9 | 0.0 | 2613.3 | 1161.5 | 3724.0 | 2613.3 | 1046.4 | 365.9 | 339.7 | 0.0 | 0.0 | 195.1 | 37.2 | 1960.0 | 0.0 | 705.6 |
| 1149+05.00 TO 1156+43.00 | 738.0 | 820.0 | 1968.0 | 0.0 | 0.0 | 2656.8 | 0.0 | 788.0 | 277.0 | 255.8 | 0.0 | 0.0 | 243.4 | 212.5 | 1476.0 | 0.0 | 532.8 |
| 1156+43.00 TO 1163+16.00 | 673.0 | 747.8 | 1794.7 | 0.0 | 0.0 | 3161.5 | 0.0 | 1040.3 | 367.5 | 340.0 | 0.0 | 0.0 | 0.0 | 193.7 | 673.0 | 0.0 | 707.5 |
| 1163+16.00 TO 1168+20.00 | 504.0 | 560.0 | 1344.0 | 0.0 | 0.0 | 1814.4 | 0.0 | 538.1 | 189.2 | 174.7 | 0.0 | 0.0 | 166.2 | 145.1 | 1008.0 | 0.0 | 363.9 |
| 1168+20.00 TO 1169+75.00 | 155.0 | 172.2 | 0.0 | 0.0 | 0.0 | 651.0 | 0.0 | 91.6 | 58.2 | 53.7 | 0.0 | 0.0 | 51.1 | 44.6 | 310.0 | 0.0 | 111.9 |
| 1169+75.00 TO 1171+05.00 | 130.0 | 144.4 | 0.0 | 0.0 | 0.0 | 546.0 | 0.0 | 7.4 | 24.4 | 45.1 | 0.0 | 0.0 | 34.4 | 37.4 | 260.0 | 66.7 | 69.5 |
| 1171+05.00 TO 1173+50.00 | 245.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1173+50.00 TO 1174+80.00 | 130.0 | 144.4 | 0.0 | 0.0 | 0.0 | 546.0 | 0.0 | 7.4 | 24.4 | 45.1 | 0.0 | 0.0 | 34.4 | 37.4 | 260.0 | 66.7 | 69.5 |
| 1174+80.00 TO 1176+35.00 | 155.0 | 172.2 | 0.0 | 0.0 | 0.0 | 651.0 | 0.0 | 91.6 | 58.2 | 53.7 | 0.0 | 0.0 | 51.1 | 44.6 | 310.0 | 0.0 | 111.9 |
| 1176+35.00 TO 1191+50.00 | 1515.0 | 1683.3 | 4040.0 | 0.0 | 0.0 | 5454.0 | 0.0 | 1617.6 | 568.7 | 525.2 | 0.0 | 0.0 | 499.6 | 436.1 | 3030.0 | 0.0 | 1093.9 |
| 1191+50.00 TO 1192+50.00 | 100.0 | 111.1 | 0.0 | 0.0 | 0.0 | 420.0 | 0.0 | 106.8 | 37.5 | 34.7 | 0.0 | 0.0 | 33.0 | 28.8 | 200.0 | 0.0 | 72.2 |
| 1192+50.00 TO 1210+50.00 | 1800.0 | 2000.0 | 4800.0 | 0.0 | 0.0 | 6480.0 | 0.0 | 1921.9 | 675.7 | 624.0 | 0.0 | 0.0 | 622.5 | 518.2 | 3600.0 | 0.0 | 1299.7 |
| 1210+50.00 TO 1211+50.00 | 100.0 | 111.1 | 0.0 | 0.0 | 0.0 | 420.0 | 0.0 | 106.8 | 37.5 | 34.7 | 0.0 | 0.0 | 33.0 | 28.8 | 200.0 | 0.0 | 72.2 |
| 1211+50.00 TO 1217+20.00 | 570.0 | 633.3 | 1520.0 | 0.0 | 0.0 | 2052.0 | 0.0 | 608.6 | 214.0 | 197.6 | 0.0 | 0.0 | 188.0 | 164.1 | 1140.0 | 0.0 | 411.6 |
| 1217+20.00 TO 1218+20.00 | 100.0 | 111.1 | 0.0 | 0.0 | 0.0 | 420.0 | 0.0 | 106.8 | 37.5 | 34.7 | 0.0 | 0.0 | 33.0 | 28.8 | 200.0 | 0.0 | 72.2 |
| 1218+20.00 TO 1225+50.00 | 730.0 | 811.1 | 1946.7 | 0.0 | 0.0 | 2628.0 | 0.0 | 779.4 | 274.0 | 253.1 | 0.0 | 0.0 | 240.7 | 210.2 | 1460.0 | 0.0 | 527.1 |
| 1225+50.00 TO 1226+50.00 | 100.0 | 111.1 | 0.0 | 0.0 | 0.0 | 420.0 | 0.0 | 106.8 | 37.5 | 34.7 | 0.0 | 0.0 | 33.0 | 28.8 | 200.0 | 0.0 | 72.2 |
| 1226+50.00 TO 1237+95.00 | 1145.0 | 1272.2 | 3053.3 | 0.0 | 0.0 | 4122.0 | 0.0 | 1222.5 | 429.8 | 396.9 | 0.0 | 0.0 | 377.6 | 329.6 | 2290.0 | 0.0 | 826.7 |

• EFFINGHAM & FAYETTE

| | | | | | | | | | | | | | |
|---|---------------------|------------|-----------|---|-------------------------------|---------------------------|------|---------|--------------------|-----------------------|--------|-----------------|--------------|
| FILE NAME = c:\pw_work\puidot\swartzw\d0186577\077469-sh-t-sch.dgn | USER NAME = swartzw | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SCHEDULE OF QUANTITIES | | | | F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | | DRAWN - | REVISED - | | SCALE: NA | SHEET NO. 11 OF 16 SHEETS | STA. | TO STA. | 70 | (26-5,26-5-1,25-1-1)R | • | 92 | 25 |
| | | CHECKED - | REVISED - | | | | | | CONTRACT NO. 74469 | | | | |
| | | DATE - | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | | | | |