

GUARDRAIL SCHEDULE LOCATION	GUARDRAIL REMOVAL	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 6A	TRAFFIC BARRIER TERMINAL, TYPE 6B	STEEL RAILING, TYPE 2399	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TERMINAL MARKERS - DIRECT APPLIED	GUARDRAIL MARKERS, TYPE A
	FOOT	EACH	EACH	EACH	FOOT	FOOT	EACH	EACH	EACH
I 70 EB									
SN 026-0079 PIER PROTECTION	438.0	0.0	0.0	1.0	0.0	175.0	1.0	1.0	4.0
SN 026-0055 PIER PROTECTION	457.0	0.0	0.0	1.0	0.0	175.0	1.0	1.0	4.0
SN 026-0023 SW CORNER	1063.0	1.0	0.0	0.0	0.0	862.5	1.0	1.0	6.0
SN 026-0023 NW CORNER	155.0	1.0	0.0	0.0	0.0	212.5	1.0	1.0	3.0
SN 026-0023 SE CORNER	1005.0	1.0	0.0	0.0	0.0	825.0	1.0	1.0	6.0
SN 026-0080 PIER PROTECTION	441.0	0.0	0.0	1.0	0.0	175.0	1.0	1.0	4.0
SN 025-0054 PIER PROTECTION	439.0	0.0	0.0	1.0	0.0	175.0	1.0	1.0	4.0
SN 025-0055 PIER PROTECTION	440.0	0.0	0.0	1.0	0.0	175.0	1.0	1.0	4.0
SN 026-0005 SW CORNER	926.0	1.0	0.0	0.0	0.0	850.0	1.0	1.0	6.0
SN 026-0005 NW CORNER	167.0	1.0	0.0	0.0	0.0	212.5	1.0	1.0	3.0
I 70 WB									
SN 026-0079 PIER PROTECTION	452.0	0.0	0.0	1.0	0.0	175.0	1.0	1.0	4.0
SN 026-0055 PIER PROTECTION	457.0	0.0	0.0	1.0	0.0	175.0	1.0	1.0	4.0
SN 026-0024 NW CORNER	1116.0	1.0	0.0	0.0	0.0	925.0	1.0	1.0	6.0
SN 026-0024 NE CORNER	1149.0	1.0	0.0	0.0	0.0	950.0	1.0	1.0	6.0
SN 026-0024 SE CORNER	378.0	1.0	0.0	0.0	0.0	212.5	1.0	1.0	3.0
SN 026-0080 PIER PROTECTION	439.0	0.0	0.0	1.0	0.0	175.0	1.0	1.0	4.0
SN 025-0054 PIER PROTECTION	438.0	0.0	0.0	1.0	0.0	175.0	1.0	1.0	4.0
SN 025-0055 PIER PROTECTION	440.0	0.0	0.0	1.0	0.0	175.0	1.0	1.0	4.0
SN 026-0006 NW CORNER	858.0	1.0	0.0	0.0	0.0	787.5	1.0	1.0	6.0
OVERHEAD STURCTURES									
SN 026-0079 SE CORNER	100.0	0.0	1.0	0.0	0.0	37.5	1.0	1.0	1.0
SN 026-0079 NE CORNER	100.0	0.0	1.0	0.0	0.0	0.0	1.0	1.0	1.0
SN 026-0079	0.0	0.0	0.0	0.0	462.0	0.0	0.0	0.0	6.0
SN 026-0079 NW CORNER	100.0	0.0	1.0	0.0	0.0	37.5	1.0	1.0	1.0
SN 026-0079 SW CORNER	100.0	0.0	1.0	0.0	0.0	0.0	1.0	1.0	1.0
SN 026-0055 SE CORNER	158.0	1.0	0.0	0.0	0.0	50.0	1.0	1.0	1.0
SN 026-0055 NE CORNER	128.0	1.0	0.0	0.0	0.0	0.0	1.0	1.0	1.0
SN 026-0055	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SN 026-0055 NW CORNER	163.0	1.0	0.0	0.0	0.0	50.0	1.0	1.0	1.0
SN 026-0055 SW CORNER	122.0	1.0	0.0	0.0	0.0	0.0	1.0	1.0	1.0
SN 026-0080 SE CORNER	100.0	0.0	1.0	0.0	0.0	37.5	1.0	1.0	1.0
SN 026-0080 NE CORNER	100.0	0.0	1.0	0.0	0.0	0.0	1.0	1.0	1.0
SN 026-0080	0.0	0.0	0.0	0.0	458.0	0.0	0.0	0.0	6.0
SN 026-0080 NW CORNER	100.0	0.0	1.0	0.0	0.0	37.5	1.0	1.0	1.0
SN 026-0080 SW CORNER	100.0	0.0	1.0	0.0	0.0	0.0	1.0	1.0	1.0
SN 025-0054 SE CORNER	100.0	0.0	1.0	0.0	0.0	37.5	1.0	1.0	1.0
SN 025-0054 NE CORNER	100.0	0.0	1.0	0.0	0.0	0.0	1.0	1.0	1.0
SN 025-0054	0.0	0.0	0.0	0.0	466.0	0.0	0.0	0.0	6.0
SN 025-0054 NW CORNER	100.0	0.0	1.0	0.0	0.0	37.5	1.0	1.0	1.0
SN 025-0054 SW CORNER	100.0	0.0	1.0	0.0	0.0	0.0	1.0	1.0	1.0
SN 025-0055 SE CORNER	100.0	0.0	1.0	0.0	0.0	37.5	1.0	1.0	1.0
SN 025-0055 NE CORNER	100.0	0.0	1.0	0.0	0.0	0.0	1.0	1.0	1.0
SN 025-0055	0.0	0.0	0.0	0.0	458.0	0.0	0.0	0.0	6.0
SN 025-0055 NW CORNER	100.0	0.0	1.0	0.0	0.0	37.5	1.0	1.0	1.0
SN 025-0055 SW CORNER	100.0	0.0	1.0	0.0	0.0	0.0	1.0	1.0	1.0
TOTALS=	13429.0	13.0	16.0	10.0	1844.0	7987.5	39.0	39.0	129.0

• EFFINGHAM & FAYETTE

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -
ci:\pw\work\p\idot\swartzw\d0186577\077469-sht-sch.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 6/5/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NA SHEET NO. 15 OF 16 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(26-5,26-5-1,25-1-1)R		92	29
CONTRACT NO. 74469			ILLINOIS FED. AID PROJECT	