

PAVING SCHEDULE

		HOT-MIX ASPHALT BINDER COURSE, 1L-19.0 FG, N90	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, 1L-19.0 FG, N90	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	HOT-MIX ASPHALT SURFACE REMOVAL, 6 1/2"	SHOULDER RUMBLE STRIPS	HOT-MIX ASPHALT SHOULDERS	BITUMINOUS MATERIALS PRIME COAT	AGGREGATE WEDGE SHOULDER, TYPE B	TEMPORARY RAMP	DESCRIPTION
EASTBOUND		QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	
STATION TO STATION		( TON)	( TON)	( TON)	( TON)	( SQ YD)	( FOOT)	( TON)	( POUND)	( TON)	( SQ FT)		
410+00.00	575+54.38	5562	5739	5562		29430	44145	16554	3296	33605	276		
80+00.00	119+00.00	1310	1352	1310		6933	10400	3900	777	7917	65		
119+00.00	124+00.00	0	0	0		0	0	0	0	0	0		018-0046 STRUCTURE/RESURF. OMISSION
124+00.00	138+50.00	487	503	487		2578	3867	1450	289	2944	24		
138+50.00	147+50.00	0	0	0		0	0	0	0	0	0		018-0048 STRUCTURE/RESURF. OMISSION
147+50.00	153+75.00	210	217	210		1111	1667	625	124	1269	10		
153+75.00	166+00.00	0	0	0		0	0	0	0	0	0		008-0050 STRUCTURE/RESURF. OMISSION
166+00.00	292+20.00	4240	4375	4240		22436	33653	10620	2513	25619	375		
TOTAL		11810	12185	11810		62488	93732	33149	6999	71353	751		
WESTBOUND		QUANTITY	QUANTITY	QUANTITY					QUANTITY				
STATION TO STATION		( TON)	( TON)	( TON)					( TON)				
410+00.00	575+54.38	5562	5739	5562		29430	44145	16554	3296	33605	276		
80+00.00	118+00.00	1277	1317	1277		6756	10133	3800	757	7714	63		
118+00.00	123+00.00	0	0	0		0	0	500	0	0	0		018-0045 STRUCTURE/RESURF. OMISSION
123+00.00	139+25.00	546	563	546		2889	4333	1625	324	3299	27		
139+25.00	146+75.00	0	0	0		0	0	0	0	0	0		018-0047 STRUCTURE/RESURF. OMISSION
146+75.00	152+75.00	202	208	202		1067	1600	600	119	1218	10		
152+75.00	165+50.00	0	0	0		0	0	1275	0	0	0		008-0049 STRUCTURE/RESURF. OMISSION
165+50.00	292+20.00	4257	4392	4257		22524	33787	11547	2523	25720	376		
TOTAL		11844	12220	11844		62666	93998	35901	7019	71556	753		
MEDIAN CROSSOVER													
STATION													
101+50.00						241			27	6	3		
242+00.00						241			27	6	3		
TOTAL						483	0	0	54	12	6		
RAMPS													
STATION TO STATION													
188+52.32		200+00.00			404	1738			195	2015	50	112	NE RAMP A
200+00.00		214+15.51			411	3275			199	2390	61	112	NW RAMP B
389+15.00		400+52.00			603	1776			358	2821	63	112	SW RAMP C
400+00.00		413+66.62			408	3200			367	2358	50	112	SE RAMP D
TOTAL					1826	9990	0	0	1119	9584	224	448	
GRAND TOTALS		23654	24405	23654	1826	135626	187730	69051	15190	152506	1734	448	