

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	THERMOPLASTIC PAVEMENT MARKING • LINE 4" WHITE	THERMOPLASTIC PAVEMENT MARKING • LINE 4" YELLOW	THERMOPLASTIC PAVEMENT MARKING • LINE 8" WHITE	THERMOPLASTIC PAVEMENT MARKING • LINE 8" YELLOW	THERMOPLASTIC PAVEMENT MARKING • LINE 12" WHITE	THERMOPLASTIC PAVEMENT MARKING • LINE 12" YELLOW	THERMOPLASTIC PAVEMENT MARKING • LINE 24" WHITE	GROOVING FOR RECESSED PAVEMENT MARKING 5'	GROOVING FOR RECESSED PAVEMENT MARKING 9'	GROOVING FOR RECESSED PAVEMENT MARKING 13'	GROOVING FOR RECESSED PAVEMENT MARKING 25'	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	EACH
IL 15 EB															
81+67.00 TO 120+50.00	3883.0	5378.8	3518.0	245.0	130.0	26.3	16.4	0.0	8896.8	375.0	42.7	0.0	1152.0	128.0	49.0
IL 15 WB															
81+50.00 TO 115+00.00	3350.0	3616.3	3305.0	365.0	130.0	71.6	0.0	22.0	6921.3	495.0	71.6	22.0	1008.0	112.0	41.0
US 45 & CURVE C															
97+92.42 TO 111+87.35	1394.9	1787.9	1318.0	230.0	110.0	6.6	13.1	22.0	3105.9	340.0	19.7	22.0	420.0	46.7	17.0
CURVE F															
2+00.00 TO 10+43.21	843.2	1054.0	530.0	313.2	0.0	0.0	0.0	0.0	1584.0	313.2	0.0	0.0	252.0	28.0	10.0
CURVE D															
3+78.53 TO 11+77.16	798.6	544.0	773.6	229.6	0.0	0.0	0.0	14.0	1317.6	229.6	0.0	14.0	0.0	0.0	0.0
CURVE B															
96+75.00 TO 106+12.19	937.2	1171.5	605.0	215.0	117.2	9.7	0.0	0.0	1776.5	332.2	9.7	0.0	288.0	32.0	10.0
TOTALS		13552.0	10050.0	1598.0	487.0	114.0	30.0	58.0	23602.0	2085.0	144.0	58.0	3120.0	347.0	127.0

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ci:\pw\work\p\idot\steffenmk\d0397316\074690-sh-t-sch.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/22/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328 821	D7 HMA RESURF 2015-9	WAYNE	12	6
CONTRACT NO. 74690			ILLINOIS FED. AID PROJECT	