

SEEDING AND EROSION CONTROL													
LOCATION		EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL BLANKET	SEEDING, CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	INLET AND PIPE PROTECTION	PERIMETER EROSION BARRIER	
STATION	OFFSET	SQ YD	SQ YD	ACRE	POUND	POUND	POUND	ACRE	POUND	FOOT	EACH	FEET	
347+90	349+36	LEFT	436	436	0.13	12	12	12	0.04	13	36	143	
349+67	352+49	LEFT	863	863	0.25	22	22	22	0.07	25	54	279	
352+81	359+88	LEFT	624	624	0.18	16	16	16	0.05	18	54	214	
355+19	358+12	LEFT	1025	1025	0.28	25	25	25	0.07	28	54	293	
358+36	359+13	LEFT	225	225	0.07	6	6	6	0.02	7	18	113	
343+83	347+62	RIGHT	1960	1960	0.52	47	47	47	0.12	52	72	444	
347+97	349+02	RIGHT	306	306	0.13	12	12	12	0.07	13	18	106	
349+37	350+03	RIGHT			0.09	8	8	8	0.09	9		66	2
350+38	350+90	RIGHT			0.07	6	6	6	0.07	7		51	2
351+22	352+90	RIGHT	695	695	0.21	19	19	19	0.07	21	36	187	
353+24	356+97	RIGHT	1737	1737	0.45	40	40	40	0.09	45	72	376	
357+21	358+53	RIGHT	476	476	0.14	12	12	12	0.04	14	54	143	
358+79	359+13	RIGHT	104	104	0.03	3	3	3	0.01	3	18	34	
TOTALS			8450	8450	2.6	230	230	230	0.8	256	486	4	2449

GRADING AND SHAPING DITCHES SCHEDULE				
LOCATION				GRADING AND SHAPING DITCHES
FT				
20+50	TO	22+75	ARNOLD DR	225.0
TOTALS				225.0

SIDEWALK SCHEDULE					
LOCATION				SIDEWALK REMOVAL	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH
STATION	TO	OFFSET	SF	SF	
355+19.5	TO	359+00.0	LT	1902.5	1902.5
TOTALS				1903	1903

PAVEMENT MARKING SCHEDULE												
LOCATION		THERMOPLASTIC PAVEMENT MARKING						RAISED REFLECTIVE PAVEMENT MARKERS		SHORT TERM PAVEMENT MARKING LANES	WORK ZONE PAVEMENT MARKING REMOVAL	
		4"				12" YELLOW DIAGONAL	LETTERS AND SYMBOLS	ONE WAY CRYSTAL	TWO WAY AMBER			
		SOLID		SKIP DASH						SF	EACH	EACH
STATION	TO	WHITE	YELLOW	WHITE	YELLOW	FT						
345+59.9	TO	346+00.0		80	10					16	33	
346+00.0	TO	346+64.0	128	225	40		61			64	203	
346+64.0	TO	347+30.0	132	132	40	40				64	125	
347+30.0	TO	348+21.4	91	183	50	50				88	139	
348+21.4	TO	357+61.0	1879	1879	470	470				904	1717	
357+61.0	TO	358+19.9	118	118	20	30				48	103	
358+19.9	TO	359+14.5	95	189	30	50				72	133	
359+14.5	TO	363+01.0		773		200				156	350	
363+01.0	TO	363+61.0		120							40	
363+61.0	TO	364+36.0	75	150				31.2			106	
346+64.0	TO	363+01.0						250		85	250	
363+01.0	TO	364+36.0							4	4		
345+59.9	TO	357+61.0								32		
357+61.0	TO	359+14.5								2		
SUB-TOTALS			2518	3849	660	840	61	281	38	89	1412	3200
TOTALS				7867			61	281	127		1412	3200

PAVEMENT MARKING REMOVAL SCHEDULE								
LOCATION			YELLOW		WHITE		PAVEMENT MARKING REMOVAL	RRPM REMOVAL
			4" SOLID	12" DIAGONAL	4" SOLID	LETTERS AND SYMBOLS		
STATION	TO	STATION	FT	FT	FT	SF	EACH	
345+59.9	TO	346+00.0	40.1				13.4	
346+00.0	TO	359+13.1					0	66
359+13.1	TO	363+01.0	1551	120			637.1	20
363+01.0	TO	363+20.2	38				12.8	1
363+20.2	TO	364+36.0	231.6		116	31.2	147	6
TOTALS						810	93	