

## PAVEMENT MARKING SCHEDULE

LOCATION: STATION TO STATION			LENGTH	PAINT PAVEMENT MARKING LINE 4"		RAISED REFLECTOR PAVEMENT MARKER TWO WAY AMBER	RAISED REFLECTOR PAVEMENT MARKER REMOVAL	SHORT TERM PAVEMENT MARKING (3 APPL)	TEMPORARY PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
				4" YELLOW SKIP DASH	4" WHITE EDGE LINES					
IL 3 (FAP 14)			(FT)	(FT)	(FT)	(EACH)	(EACH)	(FT)	(FT)	(SQ FT)
STA	TO	STA								
194+00	TO	190+00	400.0	100	800	6	5	120	900	340
190+00 (BK)	=	155+59.56 (AH)								
155+59.56	TO	355+54	19994.4	4999	39989	250	191	5998	44988	16995.4
OMISSION SN (002-0014)										
358+87	TO	391+00	3213.0	804	6426	41	27	964	7230	2731.3
SUB TOTALS				5903	47215					
TOTALS				53118		297	223	7082	53118	20067

Temporary Pavement Marking =  
Paint Pavement Marking

Work Zone Pavement Marking Removal = Removal of Temporary  
Pavement Marking and Short Term Pavement Marking

FILE NAME =	USER NAME = Stoverpg	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PAVEMENT MARKING SCHEDULE</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct\pwork\pwork\stoverpg\0166978\78205-sht-plan.dgn		DRAWN -	REVISED -			14	I36RS-4, I37RS-2	ALEXANDER	18	12
		CHECKED -	REVISED -						CONTRACT NO. 78205	
		DATE -	REVISED -		SCALE: _____	SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____		ILLINOIS FED. AID PROJECT