

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	CONSTRUCTION TYPE CODE		0005
		UNIT	TOTAL QUANTITY	ROADWAY 100% STATE
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	6	6
Z0034105	MATERIAL TRANSFER DEVICE	TON	7483	7483
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	42656	42656
40600647	LEVELING BINDER (MACHINE METHOD) IL-9.5FC, N90	TON	2501	2501
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	225	225
40600990	TEMPORARY RAMP	SQ YD	166	166
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE C, N90	TON	4982	4982
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	79	79
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	53474	53474
44000158	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"	SQ YD	6150	6150
44200176	PAVEMENT PATCHING, TYPE I, 15 INCH	SQ YD	2.7	2.7
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	533.0	533.0
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	16.0	16.0
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	1046	1046

FILE NAME *	USER NAME * #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\p\work\p101dot\brandonja\0270026\0970270-sht-plan.dgn		DRAWN -	REVISED -			960	38RS-5	JOHNSON	26	5
PLOT SCALE * 100.0000' / 1"		CHECKED -	REVISED -		SCALE:					
PLOT DATE * 6/5/2014		DATE -	REVISED -		SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.			CONTRACT NO. 78270
										ILLINOIS FED. AID PROJECT