

REMOVAL SCHEDULE

LOCATION STATION TO STATION	LENGTH	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	REMARKS
	FOOT	SQ YD	SQ YD	FOOT	
IL 13					
1808+14. TO 1809+62.	148.00	247	66		
1809+62. TO 1817+45.	783.00	1392	348		
1817+45. TO 1818+62.	117.00	208			
1827+00. TO 1830+10.98	310.98	553	138		
CURB AND GUTTER REPAIR				100	REMOVAL AND REPLACEMENT TO BE USED AS DIRECTED BY THE ENGINEER
SUBTOTALS	1359	2400	552	100	

PAVEMENT AND SHOULDER SCHEDULE

LOCATION STATION TO STATION	LENGTH	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SUBBASE GRANULAR MATERIAL, TYPE C	AGGREGATE SHOULDERS, TYPE B	STABILIZED SUB-BASE 4"	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/2"	TIE BARS 3/4"	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	PROTECTIVE COAT	REMARKS
	FOOT	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	EACH	FOOT	SQ YD	
IL 13											
1808+14. TO 1809+62.	148.00	304	8	34	271	247	49	74		296	
1809+62. TO 1817+45.	783.00	1697	40	180	1523	1392	261	392		1653	
1817+45. TO 1818+62.	117.00	208			208	208		66		208	
1827+00. TO 1830+10.98	310.98	674	16	71	605	553	104	155		657	
CURB AND GUTTER REPAIR									100		REMOVAL AND REPLACEMENT TO BE USED AS DIRECTED BY ENGINEER
SUBTOTALS	1359	2883	63	285	2607	2400	414	686	100	2814	

PAVEMENT MARKING SCHEDULE

LOCATION TO STATION	STATION	PAINT PAVEMENT MARKING - LINE 4"		SHORT TERM PAVEMENT MARKING SKIP-DASHES		REMARKS
		WHITE SOLID	YELLOW SOLID	WHITE	YELLOW	
		FOOT	FOOT			
IL 13						
1808+14. TO 1817+45.		931.00		36.00		OUTSIDE EOP
1808+14. TO 1818+62.			1048.00	40.00		INSIDE EOP
1827+00. TO 1830+10.98		310.98	310.98	12.00	28.00	INSIDE & OUTSIDE EOP
		1242	1359	48	68	
TOTALS		2601		116		