


**UN053**

REVISIONS		
NUMBER	BY	DATE



UNIVERSITY OF ILLINOIS  
 WILLARD AIRPORT  
 SAVOY, ILLINOIS

BASE BID - REALIGN AND WIDEN TAXIWAY C  
 INDEX TO SHEETS AND SUMMARY OF  
 QUANTITIES

© Copyright CMT, Inc.



DESIGN BY:	CBG
DRAWN BY:	CMT
CHECKED BY:	
APPROVED BY:	
DATE:	JUNE 27, 2014
JOB No:	13059-02-00
IL PROJ. NO.	CMI-4347
AIP PROJ. NO.	3-17-0016-XX
SHEET	02 OF 83 SHEETS

SUMMARY OF QUANTITIES			
ITEM NO.	DESCRIPTION	UNIT	QUANTITY
BASE BID			
AR108065	RGL CABLE	LF	4,450
AR108066	REIL CABLE	LF	1,040
AR108158	1/C #8 5KV UG CABLE IN UD	LF	14,175
AR108258	2/C #8 5KV UG CABLE IN UD	LF	370
AR109210	VAULT MODIFICATIONS	EA	1
AR110504	4-WAY CONCRETE ENCASED DUCT	LF	160
AR110550	SPLIT DUCT	LF	253
AR110014	4" DIRECTIONAL BORE	LF	2,450
AR110900	REMOVE DUCT	LF	280
AR110903	REMOVE CABLE MARKER	EA	9
AR125415	MITL - BASE MOUNTED	EA	89
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EA	2
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EA	6
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EA	4
AR125449	TAXI GUIDANCE SIGN, 9 CHARACTER	EA	1
AR125565	SPLICE CAN	EA	10
AR125740	RUNWAY GUARD LIGHT	EA	12
AR125901	REMOVE STAKE MOUNTED LIGHT	EA	87
AR125902	REMOVE BASE MOUNTED LIGHT	EA	109
AR125904	REMOVE TAXI GUIDANCE SIGN	EA	31
AR125921	REPLACE STAKE MOUNTED LIGHT	EA	13
AR125922	REPLACE BASE MOUNTED LIGHT	EA	3
AR125962	RELOCATE BASE MOUNTED LIGHT	EA	1
AR125975	RELOCATE RUNWAY GUARD LIGHT	EA	4
AR800242	REPLACE SIGN FACE	EA	10
AR150510	ENGINEER'S FIELD OFFICE	LS	1
AR152410	UNCLASSIFIED EXCAVATION	CY	12,500
AR152481	SHOULDER ADJUSTMENT	CY	2,100
AR156500	TEMPORARY EROSION CONTROL	LS	1
AR201670	CRACK CONTROL FABRIC	SY	1,520
AR209610	CRUSHED AGG. BASE COURSE - 10"	SY	19,870
AR401610	BITUMINOUS SURFACE COURSE	TON	5,400
AR401630	BITUMINOUS SURFACE TEST SECTION	EA	1
AR401650	BITUMINOUS PAVEMENT MILLING	SY	760
AR401921	REMOVE PAVEMENT	SY	9,800
AR403610	BITUMINOUS BASE COURSE	TON	10,970
AR403630	BITUMINOUS BASE TESTE SECTION	EA	1
AR602510	BITUMINOUS PRIME COAT	GAL	9,950
AR603510	BITUMINOUS TACK COAT	GAL	14,065
AR620520	PAVEMENT MARKING-WATERBORNE	SF	19,300
AR620525	PAVEMENT MARKING - BLACK BORDER	SF	9,200
AR620555	PREFORMED THERMOPLASTIC	SF	2,938
AR620900	PAVEMENT MARKING REMOVAL	SF	81,022
AR620910	PREFORMED THERMOPLASTIC REMOVAL	SF	1,783
AR625511	SEAL COAT	SY	19,100
AR701512	12" RCP, CLASS IV	LF	368
AR701521	21" RCP, CLASS IV	LF	72
AR701900	REMOVE PIPE	LF	320
AR705524	4" PERFORATED UNDERDRAIN W/SOCK	LF	5,730
AR705544	4" NON PERFORATED UNDERDRAIN	LF	451
AR705635	UNDERDRAIN COLLECTION STRUCTURE	EA	4
AR705640	UNDERDRAIN CLEANOUT	EA	12
AR705904	REMOVE UNDERDRAIN CLEANOUT	EA	5
AR751410	INLET	EA	3
AR751415	INLET SPECIAL	EA	1
AR751550	MANHOLE 5'	EA	2
AR751900	REMOVE INLET	EA	2
AR752421	PRECAST REINFORCED CONC. FES 21"	EA	1
AR800330	PERMANENT BARRICADES	EA	64
AR901510	SEEDING	AC	13
AR904510	SODDING	SY	5,600
AR908510	MULCHING	AC	13
AR908525	KNITTED STRAW MAT	SY	5,600
AR910200	ROADWAY SIGN	EA	1
AR910915	REMOVE ROADWAY SIGN	EA	1

Sheet List Table	
Sheet Number	Sheet Title
01	COVER SHEET
02	INDEX TO SHEETS AND SUMMARY OF QUANTITIES
03	AIRPORT SITE PLAN
04	GENERAL NOTES
05	CONSTRUCTION ACTIVITY PLAN NOTES & DETAILS
06	CONSTRUCTION ACTIVITY PLAN - INDEX
07	CONSTRUCTION ACTIVITY PLAN - PHASE 1A
08	CONSTRUCTION ACTIVITY PLAN - PHASE 1B
09	CONSTRUCTION ACTIVITY PLAN - PHASE 2
10	CONSTRUCTION ACTIVITY PLAN - PHASE 3
11	CONSTRUCTION ACTIVITY PLAN - PHASE 4A
12	CONSTRUCTION ACTIVITY PLAN - PHASE 4B
13	CONSTRUCTION ACTIVITY PLAN - PHASE 5
14	CONSTRUCTION ACTIVITY PLAN - PHASE 6
15	CONSTRUCTION ACTIVITY PLAN - PHASE 7
16	CONSTRUCTION ACTIVITY PLAN - PHASE 8
17	CONSTRUCTION ACTIVITY PLAN - PHASE 9
18	CONSTRUCTION SAFETY PHASING NOTES
19	EXISTING PAVEMENT STRUCTURES
20	EXISTING CONDITIONS AND REMOVALS - LEGEND AND NOTES
21	EXISTING CONDITIONS AND REMOVALS SHEET 1
22	EXISTING CONDITIONS AND REMOVALS SHEET 2
23	EXISTING CONDITIONS AND REMOVALS SHEET 3
24	EXISTING CONDITIONS AND REMOVALS SHEET 4
25	EXISTING CONDITIONS AND REMOVALS SHEET 5
26	PROPOSED IMPROVEMENTS
27	PROPOSED GEOMETRY SHEET 1
28	PROPOSED GEOMETRY SHEET 2
29	STAKING PLAN 1
30	TYPICAL SECTIONS 1
31	TYPICAL SECTIONS 2
32	TYPICAL SECTIONS 3
33	TYPICAL SECTIONS 4
34	PROPOSED DRAINAGE IMPROVEMENTS SHEET 1
35	PROPOSED DRAINAGE IMPROVEMENTS SHEET 2
36	DRAINAGE TABLES
37	DRAINAGE DETAILS 1
38	DRAINAGE DETAILS 2
39	UNDERDRAIN DETAILS
40	PROPOSED LIGHTING LAYOUT 1
41	PROPOSED LIGHTING LAYOUT 2
42	PROPOSED LIGHTING LAYOUT 3
43	PROPOSED CABLING LAYOUT 1
44	PROPOSED CABLING LAYOUT 2
45	PROPOSED CABLING LAYOUT 3
46	RGL AND SIGN LOCATIONS
47	ELECTRICAL DETAILS 1
48	ELECTRICAL DETAILS 2
49	ELECTRICAL DETAILS 3
50	ELECTRICAL DETAILS 4
51	ELECTRICAL DETAILS 5
52	ELECTRICAL DETAILS 6

53	ELECTRICAL VAULT PLAN
54	ALCMS GRAPHIC DISPLAY MODIFICATIONS
55	PROPOSED MARKING IMPROVEMENTS 1
56	PROPOSED MARKING IMPROVEMENTS 2
57	PROPOSED MARKING IMPROVEMENTS 3
58	PROPOSED MARKING IMPROVEMENTS 4
59	PROPOSED MARKING IMPROVEMENTS 5
60	TAXIWAY MARKING DETAILS
61	SURFACE PAINTED HOLD POSITION MARKING DETAIL
62	SURFACE PAINTED TAXIWAY MARKING
63	VORTAC CHECKPOINT DETAILS
64	TURFING PLAN AND INDEX TO CROSS SECTIONS SHEET 1
65	TURFING PLANN AND INDEX TO CROSS SECTIONS SHEET 2
66	TURFING PLAN AND INDEX TO CROSS SECTIONS SHEET 3
67	EROSION CONTROL DETAILS
68	ADDITIVE ALTERNATE - CONSTRUCTION ACTIVITY PLAN
69	ADDITIVE ALTERNATE - EXISTING CONDITIONS
70	ADDITIVE ALTERNATE - PROPOSED IMPROVEMENTS
71	ADDITIVE ALTERNATE - MARKING PLAN
72	ADDITIVE ALTERNATE - TYPICAL SECTIONS 1
73	CROSS SECTION PLAN 01
74	CROSS SECTION PLAN 02
75	CROSS SECTION PLAN 03
76	CROSS SECTION PLAN 04
77	CROSS SECTION PLAN 05
78	CROSS SECTION PLAN 06
79	CROSS SECTION PLAN 07
80	CROSS SECTION PLAN 08
81	CROSS SECTION PLAN 09
82	CROSS SECTION PLAN 10
83	CROSS SECTION PLAN 11

AR908525	KNITTED STRAW MAT	SY	5,600
AR910200	ROADWAY SIGN	EA	1
AR910915	REMOVE ROADWAY SIGN	EA	1
SUMMARY OF QUANTITIES			
ITEM NO.	DESCRIPTION	UNIT	QUANTITY
ADDITIVE ALTERNATE #1			
AS152511	SUBGRADE REPAIR	SY	500
AS201663	SAND MIX CRACK REPAIR	LF	200
AS209600	GEOTEXTILE FABRIC	SY	500
AS209606	CRUSHED AGG. BASE COURSE - 6"	SY	500
AS401610	BITUMINOUS SURFACE COURSE	TON	1,010
AS401650	BITUMINOUS PAVEMENT MILLING	SY	8,730