# SUMMARY OF QUANTITIES

LOCATION OF WORK: FAI 72 URBAN INTERSTATE SN 074-0069 (EB) & SN 074-0070 (WB) PIATT COUNTY

FUNDING BREAKOUT: 90% FEDERAL 10% STATE

CONSTRUCTION TYPE CODE: 0013

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY |
|---|---|---|---|
| | | | |
| 25000200 | SEEDING, CLASS 2 | ACRE | 0.50 |
| | | | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 45 |
| | | | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 45 |
| | | | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 45 |
| | | | |
| 25100115 | MULCH, METHOD 2 | ACRE | 0.50 |
| | | | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 50 |
| | | | |
| 31200100 | STABILIZED SUBBASE 4" | SQ YD | 756 |
| | | | |
| 40600370 | LONGITUDINAL JOINT SEALANT | FOOT | 1,982 |
| | | | |
| 40600290 | BITUMINOUS MATERIALS (TACK COAT) | POUND | 3,332 |
| | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 533 |
| | | | |
| 40603090 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90 | TON | 152 |
| | | | |
| 40604062 | HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70 | TON | 105 |
| | | | |
| 40604074 | HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "E", N90 | TON | 127 |
| 42000060 | WELDED WIRE REINFORCEMENT | SQ YD | 501 |
| 42000080 | PAVEMENT CONNECTOR (PCC) FOR BRIDGE APPROACH SLAB | SQ YD | 838 |
| | | | |

2

MODEL: Summary of Quantities [Sheet]
FILE NAME: m:\Support\IDOT_CONNECT\Con guration\WorkSpaces\IDOTCAD CONNECT\WorkSets\2564.4 Piatt Bridge Replacement\CADD Data\CAD Sheets\D570024-sht-SOQ.dgn

CEC Cummins Engineering Corporation
ENGINEERS & SURVEYORS

| | | | |
|---|---|---|---|
| JOB = 2564.4 | DESIGNED - CDS | REVISED - | |
| FILE NAME = D570024-sht-SOQ.dgn | DRAWN - CDS | REVISED - | |
| PLOT SCALE = $SCALE$ | CHECKED - CGF | REVISED - | |
| PLOT DATE = 3/12/2025 | DATE - 1/09/2025 | REVISED - | |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 72 | (74-68VB)B | PIATT | 93 | 3 |

CONTRACT NO. 70024

ILLINOIS FED. AID PROJECT

2 REV. 7/21/25