

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130N+3 (11)	DUPAGE	141	5
STA.	TO STA.			
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

60R46

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				80% FED 20% STATE	100% WEST CHICAGO FIRE PROTECTION	80% FED, 10% STATE 5% W CHICAGO, 5% DUPAGE CO		80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
				ROADWAY		TRAFFIC SIGNALS		INTERCONNECT		LIGHTING
				0003		0021		0021		0021
				URBAN	POWIS ROAD	POWIS ROAD	PHEASANT RUN	NORTH AVE	URBAN	
25200200	SUPPLEMENTAL WATERING	UNIT	3	3						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1160	1160						
28000400	PERIMETER EROSION BARRIER	FOOT	2845	2845						
28000500	INLET AND PIPE PROTECTION	EACH	5	5						
28000510	INLET FILTERS	EACH	13	13						
28100107	STONE RIPRAP, CLASS A4	SQ YD	24	24						
28200200	FILTER FABRIC	SQ YD	24	24						
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	5624	5624						
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	5624	5624						
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	565	565						
40600300	AGGREGATE (PRIME COAT)	TON	8.7	8.7						
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	4311	4311						
42001300	PROTECTIVE COAT	SQ YD	5454	5454						
44000100	PAVEMENT REMOVAL	SQ YD	1042	1042						

* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

VERT: NONE
 SCALE: HORIZ: NONE
 DATE: FEBRUARY 1, 2013

DRAWN BY: AFC
 CHECKED BY: NJH

S00-02

