

F.A.P. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307 130N-3 (1)	DUPAGE	141	6
STA. TO STA.	ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

60R46

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				80% FED 20% STATE	100% WEST CHICAGO FIRE PROTECTION	80% FED, 10% STATE 5% W CHICAGO, 5% DUPAGE CO		80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
				ROADWAY		TRAFFIC SIGNALS		INTERCONNECT		LIGHTING
				0003		0021		0021		0021
				URBAN	POWIS ROAD	POWIS ROAD	PHEASANT RUN	NORTH AVE	URBAN	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	320	320						
44201690	CLASS D PATCHES, TYPE I, 4 INCH	SQ YD	1	1						
44201692	CLASS D PATCHES, TYPE II, 4 INCH	SQ YD	11	11						
44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	382	382						
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	219	219						
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	718	718						
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	92	92						
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4						
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1						
54260311	TRAVERSABLE PIPE GRATE	FOOT	47.75	47.75						
54261448	CONCRETE END SECTION, STANDARD 542001, 48", 1:4	EACH	1	1						
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	27	27						
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	287	287						
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	10	10						

* DENOTES SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

S00-03

SCALE: VERT: NONE
 HORIZ: NONE
 DATE: FEBRUARY 1, 2013

DRAWN BY: AFC
 CHECKED BY: NJH