

F.A.P. DIST. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130N-3 (11)	DUPAGE	141	10
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

60R46

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				80% FED 20% STATE	100% WEST CHICAGO FIRE PROTECTION	80% FED, 10% STATE 5% W CHICAGO, 5% DUPAGE CO		80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
				ROADWAY	TRAFFIC SIGNALS		INTERCONNECT		LIGHTING	
				0003	0021		0021		0021	
				URBAN	POWIS ROAD	POWIS ROAD	PHEASANT RUN	NORTH AVE	URBAN	
81400200	HEAVY-DUTY HANDHOLE	EACH	1			1				
81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	1250							1250
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	7							7
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	2							2
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	5							5
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	65							65
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	5							5
84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	3							3
85000400	MAINTENANCE OF TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1				
86400100	TRANSCIVER - FIBER OPTIC	EACH	1			1				
87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	5052						5052	
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5029						5029	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1220			1220				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	5062			5062				

* DENOTES SPECIALTY ITEM

AECOM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE
 HORIZ: NONE
 DATE: FEBRUARY 1, 2013

DRAWN BY: AFC
 CHECKED BY: NJH

S00-07