

F.A.P. RITE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130M-3 (11)	DUPAGE	141	12
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

60R46

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				80% FED 20% STATE	100% WEST CHICAGO FIRE PROTECTION	80% FED, 10% STATE 5% W CHICAGO, 5% DUPAGE CO		80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	
				ROADWAY 0003	TRAFFIC SIGNALS 0021			INTERCONNECT 0021		LIGHTING 0021	
				URBAN	POWIS ROAD	POWIS ROAD	PHEASANT RUN	NORTH AVE	URBAN		
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	46			46					
87900200	DRILL EXISTING HANDHOLE	EACH	10			10					
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	17			17					
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	6			6					
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	23			23					
88500100	INDUCTIVE LOOP DETECTOR	EACH	15			15					
88500700	PREFORMED DETECTOR LOOP	FOOT	510			510					
89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	4		4						
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1		1						
89502200	MODIFY EXISTING CONTROLLER	EACH	1				1				
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1				1				
20013798	CONSTRUCTION LAYOUT	LSUM	1	1							
20030850	TEMPORARY INFORMATION SIGNING	SQ FT	358	358							
20033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	9							9	

* DENOTES SPECIALTY ITEM

14



S00-09

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE
 HORIZ: NONE
 DATE: FEBRUARY 1, 2013

DRAWN BY: AFC
 CHECKED BY: NJH