

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130N-3 (11)	DUPAGE	141	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

60R46

### ROADWAY ITEMS SCHEDULE

	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	AGGREGATE SUBGRADE IMPROVEMENT 12"	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	PROTECTIVE COAT	AGGREGATE SHOULDERS, TYPE B 10"	PORTLAND CEMENT CONCRETE SHOULDERS 10"	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6-12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6-24	CONCRETE MEDIAN, TYPE S9-6.06
	SQ YD	SQ YD	SC YD	GALLON	TON	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	FOOT	SQ FT
RDWY-5	562	562	562	57	0.9	430	549	-	61	96.3	105.7	-
RDWY-7	1,212	1,212	1,212	122	1.9	998	1,187	29	89	-	167.9	384
RDWY-14	1,483	1,483	1,483	149	2.3	1,178	1,446	-	-	-	591.7	629
RDWY-15	2,367	2,367	2,367	237	3.6	1,704	2,272	190	568	-	-	-
<b>TOTAL</b>	<b>5,624</b>	<b>5,624</b>	<b>5,624</b>	<b>565</b>	<b>8.7</b>	<b>4,311</b>	<b>5,454</b>	<b>219</b>	<b>718</b>	<b>96.3</b>	<b>865.3</b>	<b>1,013</b>
<b>ROUNDED TOTAL <sup>1</sup></b>										<b>96.5</b>	<b>865.5</b>	

**NOTES:**  
 1. PER ILLINOIS BDE MANUAL, COMBINATION CONCRETE CURB AND GUTTER IS ROUNDED TO THE NEAREST 0.50 FOOT.

### ROADWAY REMOVAL SCHEDULE

	PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	CLASS D PATCHES, TYPE I, 4 INCH	CLASS D PATCHES, TYPE II, 4 INCH	CLASS D PATCHES, TYPE IV, 4 INCH
	SQ YD	FOOT	SQ YD	SQ YD	SQ YD
RDWY-5	383	126	-	-	-
RDWY-7	234	194	-	-	382
RDWY-14	104	-	-	11	-
RDWY-15	321	-	1	-	-
<b>TOTAL</b>	<b>1,042</b>	<b>320</b>	<b>1</b>	<b>11</b>	<b>382</b>

### EARTHWORK SCHEDULE

	EARTH EXCAVATION	*TOTAL EARTH EXCAVATION ADJUSTED FOR SHRINKAGE <sup>1</sup>	*EMBANKMENT	*EARTHWORK BALANCE WASTE OR SHORTAGE(±)	FURNISHED EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
NORTH AVE	317	270	44	226	-226	41
POWIS	685	583	2,632	-2,049	2,049	1,926
<b>TOTAL</b>	<b>1,002</b>	<b>853</b>	<b>2,676</b>	<b>-1,823</b>	<b>1,823</b>	<b>1,967</b>
<b>ROUNDED TOTAL <sup>2</sup></b>	<b>1,005</b>				<b>1,825</b>	<b>1,970</b>

**NOTES:**  
 \* THIS IS NOT A PAY ITEM  
 1. ESTIMATED SHRINKAGE FACTOR = 15%  
 2. PER ILLINOIS BDE MANUAL, EARTH EXCAVATION, FURNISHED EXCAVATION, AND TOPSOIL EXCAVATION AND PLACEMENT IS ROUNDED TO THE NEAREST 5 CU YD.

### LANDSCAPING SCHEDULE

	COMPOST FURNISH AND PLACE, 2"	SEEDING, CLASS 2A	SEEDING, CLASS 4	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	EROSION CONTROL BLANKET	SODDING, SALT TOLERANT	SUPPLEMENTAL WATERING	SEEDING, CLASS 4B (MODIFIED)
	SQ YD	ACRE	ACRE	POUND	POUND	POUND	SQ YD	SQ YD	UNIT	ACRE
LSCP-3	-	0.08	-	11	11	11	654	295	3.0	-
LSCP-4	47	0.40	0.01	37	37	37	948	-	-	-
LSCP-9	440	1.48	-	142	142	142	1,526	-	-	0.10
<b>TOTAL</b>	<b>487</b>	<b>1.96</b>	<b>0.01</b>	<b>190</b>	<b>190</b>	<b>190</b>	<b>10,128</b>	<b>295</b>	<b>3.0</b>	<b>0.10</b>
<b>ROUNDED TOTAL <sup>2</sup></b>		<b>2.00</b>	<b>0.25</b>							<b>0.25</b>

**NOTES:**  
 1. TOPSOIL FURNISH AND PLACE, 4" IS LESS THAN TOPSOIL EXCAVATION AND PLACEMENT SO THIS PAY ITEM WILL NOT BE NEEDED. THE TOPSOIL WILL REUSED AND PLACED AT LOCATIONS ON THE PLANS.  
 2. PER ILLINOIS BDE MANUAL, SEEDING TOTAL IS ROUNDED TO THE NEAREST 0.25 ACRE.



REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)
NAME	DATE	
		SCHEDULE OF ROADWAY QUANTITIES

SCALE: VERT: NONE  
 HORIZ: NONE  
 DATE: FEBRUARY 1, 2013

DRAWN BY: AFC  
 CHECKED BY: NJH

SCH-1