



**CONSTRUCTION NOTES**

- ① RELOCATE EXISTING EVP DETECTOR UNIT AND CONFIRMATION BEACON TO NEW MAST ARM

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

- 6 EACH SIGNAL HEAD, 1-FACE, 3-SECTION
- 2 EACH SIGNAL HEAD, 1-FACE, 5-SECTION
- 1 EACH SIGNAL HEAD, 2-FACE, 3-SECTION
- 2 EACH PEDESTRIAN SIGNAL HEAD, 1-FACE
- 1 EACH PEDESTRIAN SIGNAL HEAD, 2-FACE
- 3 EACH PEDESTRIAN PUSHBUTTON
- 4 EACH TRAFFIC SIGNAL BACKPLATE
- 1 EACH MAST ARM ASSEMBLY AND POLE
- 3 EACH TRAFFIC SIGNAL POST

NOTE:  
SEE SHEET 30 FOR SIDEWALK AND  
DETECTABLE WARNING DETAILS.

NOTE:  
THE CONTRACTOR SHALL BE REQUIRED  
TO MAINTAIN THE OPERATION OF  
TRAFFIC SIGNALS AT ALL TIMES.

TS# 1315

PREPARED BY:  
**CEMCON, Ltd.**  
Consulting Engineers, Land Surveyors & Planners  
2280 White Oak Circle, Suite 100  
Aurora, Illinois 60504-9675  
Ph: 630.862.2100 Fax: 630.862.2199  
E-Mail: cadd@cemcon.com Website: www.cemcon.com

FILE NAME =  
MICROST\352103\ US 14 @  
PLUM SIG REM.DGN>>

USER NAME = JGC  
PLOT SCALE = 1"=20'  
PLOT DATE = 03-07-13

DESIGNED - KK  
DRAWN - RDS/JGC  
CHECKED - BPT  
DATE - 03-07-13

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REMOVAL PLAN  
U.S. ROUTE 14 (NORTHWEST HWY.) AT PLUM GROVE ROAD**

SCALE: 1"=20' SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	2012-042 TS	COOK	36	18
CONTRACT NO. 60T90				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				