



SIGN "A"



R10-11A
30" x 36"
(2 EACH)

NOTE:
THE CONTRACTOR SHALL BE REQUIRED
TO MAINTAIN THE OPERATION OF
TRAFFIC SIGNALS AT ALL TIMES.

NOTE:
THE TRAFFIC SIGNAL CONTROL
EQUIPMENT FOR THIS PROJECT
SHALL BE "ECONOLITE" TO MATCH
THE EXISTING ADJACENT SYSTEM.

NOTE:
RELOCATE EXISTING MAST ARM SIGNS
TO NEW MAST ARMS.

NOTE:
SEE SHEET 30 FOR SIDEWALK, CROSSWALKS
AND DETECTABLE WARNING DETAILS.



TS# 1315

PREPARED BY:
CEMCON, Ltd.
Consulting Engineers, Land Surveyors & Planners
2280 White Oak Circle, Suite 100
Aurora, Illinois 60504-9675
Ph: 630.862.2100 Fax: 630.862.2199
E-Mail: cadd@cemcon.com Website: www.cemcon.com

FILE NAME =
MICROST\352103\ US 14 @
PLUM SIG MOD.DGN>>

USER NAME = JGC
PLOT SCALE = 1"=20'
PLOT DATE = 03-07-13

DESIGNED - KK
DRAWN - RDS/JGC
CHECKED - BPT
DATE - 03-07-13

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TRAFFIC SIGNAL MODERNIZATION PLAN
U.S. ROUTE 14 (NORTHWEST HWY.) AT PLUM GROVE ROAD**

SCALE: 1"=20' SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	2012-042 TS	COOK	36	19
CONTRACT NO. 60T90				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				