



CONSTRUCTION NOTES

① RELOCATE EXISTING EVP DETECTOR UNIT AND CONFIRMATION BEACON TO NEW MAST ARM

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

- 8 EACH SIGNAL HEAD, 1-FACE, 3-SECTION
- 4 EACH SIGNAL HEAD, 1-FACE, 5-SECTION
- 4 EACH PEDESTRIAN SIGNAL HEAD, 2-FACE
- 4 EACH PEDESTRIAN PUSHBUTTON
- 8 EACH TRAFFIC SIGNAL BACKPLATE
- 2 EACH MAST ARM ASSEMBLY AND POLE

NOTE:
SEE SHEET 30 FOR SIDEWALK, CROSSWALKS AND DETECTABLE WARNING DETAILS.

NOTE:
THE CONTRACTOR SHALL BE REQUIRED TO MAINTAIN THE OPERATION OF TRAFFIC SIGNALS AT ALL TIMES.

TS# 1190

PREPARED BY:

CEMCON, Ltd.
 Consulting Engineers, Land Surveyors & Planners
 2280 White Oak Circle, Suite 100
 Aurora, Illinois 60504-9675
 Ph: 630.862.2100 Fax: 630.862.2199
 E-Mail: cadd@cemcon.com Website: www.cemcon.com

FILE NAME = MICROST\352103\ US 14 @ BENTON SIG REM.DGN	USER NAME = JGC	DESIGNED - BPT	REVISED -
		DRAWN - RDS/JGC	REVISED -
	PLOT SCALE = 1"=20'	CHECKED - BPT	REVISED -
	PLOT DATE = 03-07-13	DATE - 03-07-13	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**REMOVAL PLAN
U.S. ROUTE 14 (NORTHWEST HWY.) AT BENTON STREET**

SCALE: 1"=20' SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	2012-042 TS	COOK	36	21
CONTRACT NO. 60T90				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				