



SCHEDULE OF QUANTITIES

QUAN.	UNIT	ITEM
1	EACH	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
9	EACH	PEDESTRIAN PUSH-BUTTON
1	EACH	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT

REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT
 THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

QUANTITY	UNIT	DESCRIPTION
9	EACH	PEDESTRIAN PUSHBUTTON

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE".

I.D.O.T. TRAFFIC SIGNAL INSTALLATION ELECTRICAL SERVICE REQUIREMENTS				TOTAL WATTAGE
TYPE	NO. OF LAMPS (INCAND)	WATTAGE	LED % OPERATIONS	
SIGNAL (RED)	31	17	0.50	263.50
(YELLOW)	31	25	0.25	193.75
(GREEN)	31	15	0.25	116.25
ARROW	16	12	0.10	19.20
PED. SIGNAL CONTROLLER	8	25	1.00	200.00
ILLUM. SIGN	1	100	1.00	100.00
LUMINAIRE	6	25	0.05	7.50
VIDEO SYSTEM		250	0.50	
		150	1.00	
FLASHER			0.50	
ENERGY COSTS TO:			TOTAL	900.20

VILLAGE OF MOUNT PROSPECT
 50 SOUTH EMERSON STREET
 MOUNT PROSPECT, ILLINOIS 60056

ENERGY SUPPLY - CONTACT: DAVE SCHACHT
 PHONE: (630) 437-2129
 COMPANY: COMED

CABLE PLAN