

90% FED.  
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY	BRIDGE	RETAINING WALL	LIGHTING	TRAFFIC SIGNALS	UTILITY	
				0004 URBAN	0011 016-1709	0040 016-1724	0021 URBAN	0021 URBAN	0043 URBAN	
44213200	SAW CUTS	FOOT	574	574						
44213204	TIE BARS 3/4"	EACH	201	201						
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1				
△ 50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1							1
<del>50100400</del>	<del>REMOVAL OF EXISTING STRUCTURES NO. 2</del>	<del>EACH</del>	<del>1</del>							
50102400	CONCRETE REMOVAL	CU YD	83			68				15
50157300	PROTECTIVE SHIELD	SO YD	1439			1439				
50200100	STRUCTURE EXCAVATION	CU YD	148			144				4
50300225	CONCRETE STRUCTURES	CU YD	1034.1	6.5		853.7		158.9		15
50300255	CONCRETE SUPERSTRUCTURE	CU YD	766.5			766.5				
50300260	BRIDGE DECK GROOVING	SO YD	1287			1287				
50300285	FORM LINER TEXTURED SURFACE	SO FT	1732			1732				
50300300	PROTECTIVE COAT	SO YD	2340	20		2237		83		
△ 50500305	ERECTING STRUCTURAL STEEL	L SUM	1							1
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	42,810			42,810				
50500505	STUD SHEAR CONNECTORS	EACH	10,044			10044				

\* DENOTES SPECIALTY ITEM

\*\* DENOTES NON-PARTICIPATING ITEM

△ Rev. 7-19-13

Rev.



0160W25-shc-500  
USER NAME \* pimsarno  
PLOT SCALE \* 1:8000 / 1" = 100'  
PLOT DATE \* 5/16/2013

DESIGNED - JWM  
DRAWN - JWM  
CHECKED - AC  
DATE - 5/14/2013

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 4 OF 21 SHEETS STA. TO STA.

F.A.I. RTE. 90/94/290	SECTION 2013-007R	COUNTY COOK	TOTAL SHEETS 317	SHEET NO. 8
CONTRACT NO. 60W25				

ILLINOIS FED. AID PROJECT

FILE PATH: P:\38892\p1\p1\Lawson\online\local\PM\EC\0428\Documents\81\America\Transportation\60269938\_Cricle\Phase II\800\_0601\086\_Roadwork\Sheet\50W25-shc-500