CODE NO.	ITEM	UNIT	90% FED. 10% STATE URBAN TOTAL QUANTITY	CONSTRUCTION CODE: ROADWAY 0004 URBAN	BRIDGE 0011 016-1709	RETAINING WALL 0040 016-1724		LIGHTING 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	UTILITY 0043 URBAN
50800105	REINFORCEMENT BARS	POUND	398,156		351,016	45,080				2,060
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	401,200	620	362,430	38,150				
50800515	BAR SPLICERS	EACH	1031		1031					
51500100	NAME PLATES	EACH	1		1					
51602000	PERMANENT CASING	FOOT	5691		5113	578				
51603000	DRILLED SHAFT IN SOIL	CU YD	1729		1470	259				
* 51604000	DRILLED SHAFT IN ROCK	CU YD	42		42					
52000110	PREFORMED JOINT STRIP SEAL	FOOT	124		124					
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24		24					
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12		12					
52100510	ANCHOR BOLTS, 3/4"	EACH	41			25				16
52100520	ANCHOR BOLTS, 1"	EACH	72		72					
52100540	ANCHOR BOLTS, 1 1/2"	EACH	24		24					
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	69	69						
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	347	347						
~~550A0360~~	~~STORM SEWERS, CLASS A, TYPE 2 15"~~	~~FOOT~~	~~160~~	~~160~~						
55100500	STORM SEWER REMOVAL 12"	FOOT	86	86						

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM

Rev. 7-19-13 Rev.

AECOM
303 EAST WACKER DRIVE, SUITE 1400
CHICAGO, IL 60601-5276
PHONE: (312) 373-7700 FAX: (312) 373-6800

06BW25-sht-SOD	DESIGNED - JWM	REVISED -	
USER NAME = pimsorno	DRAWN - JWM	REVISED -	
PLOT SCALE = 1.0000 ' / in.	CHECKED - AC	REVISED -	
PLOT DATE = 5/16/2013	DATE - 5/14/2013	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 5 OF 21 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-007R	COOK	317	9

CONTRACT NO. 60W25
ILLINOIS FED. AID PROJECT

FILE PATH = pw:\\398939-pwint.aecomonline.local:PWAECOM03\Documents\01 Americas\Transportation\60259938 Circle\Phase II\200 CAD\806 Roadway\Sheets\60W25 Contract\D160W25-sht-SOD