

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY	BRIDGE	RETAINING WALL	LIGHTING	TRAFFIC SIGNALS	UTILITY	
				0004 URBAN	0011 016-1709	0040 016-1724	0021 URBAN	0021 URBAN	0043 URBAN	
* X0370021	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID (CDOT)	EACH	1						1	
* X0370022	ELECTRICAL HANDHOLE, HEAVY DUTY, 36", 24" FRAME AND LID (CDOT)	EACH	1						1	
* X0370023	ELECTRICAL MANHOLE, 3' X 4' X 4', 24" FRAME AND LID (CDOT)	EACH	2				1		1	
* X0370028	HARNESS CABLE, NO. 16 B/C (CDOT)	FOOT	340						340	
* X0370031	POLE, STEEL, ANCHOR BASE, 12-1/2" DIA. 3-GAUGE, 34'-6" (CDOT)	EACH	2						2	
* X0370042	VIDEO CABLE HARNESS (CDOT)	EACH	3						3	
* X0370044	VIDEO DETECTION POWER SUPPLY (CDOT)	EACH	1						1	
* X0370047	INSTALL LIGHT POLE, MAST ARM AND LUMINAIRE (CHICAGO)	EACH	12						12	
* X0370049	UNDERGROUND CONDUIT, PVC, 2" DIA., SCHEDULE 80 (CDOT)	FOOT	410						410	
* X0370050	ADVANCED TRANSPORTATION CONTROLLER, TRAFFIC, 16 LOAD BAY, P CABINET (CDOT)	EACH	1						1	
* X0370052	ELECTRIC CABLE IN CONDUIT NO. 4, 2/C (CDOT)	FOOT	97						97	
* X0370053	ELECTRIC CABLE IN CONDUIT, NO. 14 3/C, SHIELDED (CDOT)	FOOT	387						387	
* X0370054	INTERFACE PANEL, 4 CAMERA (CDOT)	EACH	1						1	
* X0370057	MAST ARM, STEEL, MONOTUBE 20 FT. (CDOT)	EACH	3						3	

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

Rev. 7-19-13



DIGW25-sh1-S00
 USER NAME = pmsarino
 PLOT SCALE = 1/8" = 1'-0"
 PLOT DATE = 5/16/2013

DESIGNED - JWM
 DRAWN - JWM
 CHECKED - AC
 DATE - 5/14/2013

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCALE: SHEET 16 OF 21 SHEETS STA. TO STA.

F.A.I. RTE. 90/94/290 SECTION 2013-007R COUNTY COOK TOTAL SHEETS 317 SHEET NO. 20 CONTRACT NO. 60W25 ILLINOIS FED. AID PROJECT

FILE PATH: \\198833-pun1-lascoment\line\local\pwc\CDOT\Documents\Illinois\Phase II\030_CAD\1006_Plan\Shasta\60W25_Contract\0160W25-sh1-S00