

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY	BRIDGE	RETAINING WALL	LIGHTING	TRAFFIC SIGNALS	UTILITY	
				0004 URBAN	0011 016-1709	0040 016-1724	0021 URBAN	0021 URBAN	0043 URBAN	
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	34	34						
Z0062456	TEMPORARY PAVEMENT	SO YD	1044	1044						
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SO FT	1398		1332	66				
Z0076600	TRAINEES	HOUR	0							
X0370069	COMBINED SEWER (EXTRA STRENGTH VITRIFIED CLAY PIPE) 8 INCH (CDOT)	FOOT	26	26						
X0370070	COMBINED SEWER (WATER MAIN REQUIREMENTS) 8 INCH (CDOT)	FOOT	92	92						
X0370071	COMBINED SEWER (WATER MAIN REQUIREMENTS) 12 INCH (CDOT)	FOOT	54	54						
X0370072	COMBINED SEWER (WATER MAIN REQUIREMENTS) 24 INCH (CDOT)	FOOT	20	20						
X0327615	COMBINED SEWER REMOVAL 8"	FOOT	83	83						
X6640704	TEMPORARY CHAIN LINK FENCE WITH SCREENING, 4'	FOOT	274	274						
* X0370073	REMOVE AND REINSTALL EXISTING MAST AND LUMINAIRE (CDOT)	EACH	3				3			
* X0370074	RACKING CABLES IN MANHOLE OR HANDHOLE (CDOT)	EACH	2				2			
X0370075	GROUND ROD, 3/4" X 10'-0" LENGTH (CDOT)	EACH	7				7			
* X0370075	UNDERGROUND CONDUIT, PVC, 4" DIA., SCHEDULE 80 (CDOT)	FOOT	420				420			
** X0370076	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM (CDOT)	FOOT	18						18	

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

Rev. 7-19-13

Rev.



DIG0425-sh1-500
USER NAME * pmsarno
PLOT SCALE * 1/8" = 1' / in.
PLOT DATE * 5/16/2013

DESIGNED - JWM
DRAWN - JWM
CHECKED - AC
DATE - 5/14/2013

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 20 OF 21 SHEETS STA. TO STA.

F.A.I. RTE. 90/94/290	SECTION 2013-007R	COUNTY COOK	TOTAL SHEETS 317	SHEET NO. 24
CONTRACT NO. 60W25				
ILLINOIS FED. AID PROJECT				

FILE PATH: I:\388074\pms\1\pms\mon\line\local\pms\CDOT\Documents\A\1\des\pms\Transportation\602099138_Circle\Phase II\1803_CAD\086_Roadway\Sheet\60W25_Contract\0186W25-sh1-500