

90% FED.  
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY 0004 URBAN	BRIDGE 0011 016-1709	RETAINING WALL 0040 016-1724	LIGHTING 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	UTILITY 0043 URBAN	
50800105	REINFORCEMENT BARS	POUND	390,156		351,016	45,080				2,060
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	401,200	620	362,430	38,150				
50800515	BAR SPLICERS	EACH	1031		1031					
51500100	NAME PLATES	EACH	1		1					
51602000	PERMANENT CASING	FOOT	1274		1274					
51603000	DRILLED SHAFT IN SOIL	CU YD	1729		1470	259				
* 51604000	DRILLED SHAFT IN ROCK	CU YD	42		42					
52000110	PREFORMED JOINT STRIP SEAL	FOOT	124		124					
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24		24					
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12		12					
52100510	ANCHOR BOLTS, 3/4"	EACH	41			25				16
52100520	ANCHOR BOLTS, 1"	EACH	72		72					
52100540	ANCHOR BOLTS, 1 1/2"	EACH	24		24					
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	69	69						
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	347	347						
<del>550A0360</del>	<del>STORM SEWERS, CLASS A, TYPE 2 15"</del>	<del>FOOT</del>	<del>160</del>	<del>160</del>						
55100500	STORM SEWER REMOVAL 12"	FOOT	86	86						

\* DENOTES SPECIALTY ITEM

\*\* DENOTES NON-PARTICIPATING ITEM

Rev. 7-30-13

Rev. 7-19-13

Rev.

FILE PATH: ... \3886939\_Punch\Personnel\Line\John.Lamson\Line\John.Lamson\Documents\81.dwg; User: John.Lamson; Title: 60W25 - Final; Date: 5/15/2013 10:50:53 AM



DIGW25-shr-500  
USER NAME: jlamson  
PLOT SCALE: 1:8000' / 1" = 8000'  
PLOT DATE: 5/15/2013

DESIGNED - JWM  
DRAWN - JWM  
CHECKED - AC  
DATE - 5/14/2013  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 5 OF 21 SHEETS STA. TO STA.

F.A.I. RTE. 90/94/290	SECTION 2013-007R	COUNTY COOK	TOTAL SHEETS 317	SHEET NO. 9
CONTRACT NO. 60W25			ILLINOIS FED. AID PROJECT	