

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY	BRIDGE	RETAINING WALL	LIGHTING	TRAFFIC SIGNALS	UTILITY	
				0004 URBAN	0011 016-1709	0040 016-1724	0021 URBAN	0021 URBAN	0043 URBAN	
44213200	SAW CUTS	FOOT	508	508						
44213204	TIE BARS 3/4"	EACH	201	201						
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1					
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1				
50102400	CONCRETE REMOVAL	CU YD	142.9			70				72.9
50157300	PROTECTIVE SHIELD	SO YD	1895		1895					
50200100	STRUCTURE EXCAVATION	CU YD	157		157					
50300225	CONCRETE STRUCTURES	CU YD	1032.5	6.5	848.6	115.9				61.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	766.2		766.2					
50300260	BRIDGE DECK GROOVING	SO YD	1287		1287					
50300285	FORM LINER TEXTURED SURFACE	SO FT	4635		4168	467				
50300300	PROTECTIVE COAT	SO YD	2351	20	2237	94				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1					
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6340			6340				
50500505	STUD SHEAR CONNECTORS	EACH	10,044		10044					

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

FILE PATH = P:\389331\count1\asce\online\local\PROJECTS\Documents\101_AmericanTransportation\62629938_Civil\Phase_1\1000_CAD\005_Quant\Sheet\016R25_Contract\016R25.tbl-500



DIGW25-411-500
USER NAME = jlm30rpd
PLOT SCALE = 1/8"=1'-0"
PLOT DATE = 5/10/2013

DESIGNED - JWM
DRAWN - JWM
CHECKED - AC
DATE - 5/14/2013

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 4 OF 21 SHEETS STA. TO STA.

F.A.I. RTE. 90/94/290	SECTION 2013-007R	COUNTY COOK	TOTAL SHEETS 317	SHEET NO. 8
CONTRACT NO. 60W25			ILLINOIS FED. AID PROJECT	

Rev.