

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY	BRIDGE	RETAINING WALL	LIGHTING	TRAFFIC SIGNALS	UTILITY	
				0004 URBAN	0011 016-1709	0040 016-1724	0021 URBAN	0021 URBAN	0043 URBAN	
* X0370058	MAST ARM, STEEL, MONOTUBE 26 FT. (CDOT)	EACH	1						1	
* X0370063	SERVICE INSTALLATION, 100 AMPERE (CDOT)	EACH	1						1	
* X0370064	UNDERGROUND CONDUIT, PVC, 3" DIA. SCHEDULE 80 (CDOT)	FOOT	603				300		363	
* X0370065	VIDEO DETECTION CARD RACK, FOUR CAMERA (CDOT)	EACH	1						1	
* X0370068	CONCRETE FOUNDATION, 24" DIAMETER, 1 1/4" ANCHOR RODS, 15" BOLT CIRCLE (CDOT)	EACH	7				6		1	
X2020502	BRACED EXCAVATION	CU YD	6372		4770	381				1221
X4240800	DETECTABLE WARNINGS (SPECIAL)	SO FT	98	80	18					
X4404000	PARKING LOT PAVEMENT REMOVAL	SO YD	61	61						
X5011100	FOUNDATION REMOVAL	EACH	12	12						
X5091730	BRIDGE FENCE RAILING (SPECIAL)	FOOT	180		180					
X5509900	ABANDON AND FILL EXISTING STORM SEWER	FOOT	59	59						
** X5537700	STORM SEWERS TO BE CLEANED 18"	FOOT	227	227						
** X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	138	138						
* X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	58	58						
X6020083	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	3	3						
X6020270	MANHOLES TYPE B, 4' DIA., TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	EACH	1	1						

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM



303 EAST WACKER DRIVE, SUITE 1100
CHICAGO, IL 60601-5276
PHONE: (312) 312-1700 FAX: (312) 312-1800

DWG# 25-sh1-500
USER NAME * pmsbrno
PLOT SCALE * 1:8000 1/2" = 1'
PLOT DATE * 5/16/2013

DESIGNED - JWM
DRAWN - JWM
CHECKED - AC
DATE - 5/14/2013

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 17 OF 21 SHEETS STA. TO STA.

F.A.I. RTE. 90/94/290	SECTION 2013-007R	COUNTY COOK	TOTAL SHEETS 317	SHEET NO. 21
CONTRACT NO. 60W25			ILLINOIS FED. AID PROJECT	

Rev.

FILE PATH: \\s11288231\public\ascomp\jms\local\pwc\0808\Documents\17 Amer\cost\trngpr\station\628289438_Circle Phase_IL\1008_CAD\008_Roadway\Sheet\16125_Contract\1016125-sh1-500