

REMOVAL SCHEDULE

LOCATION	STATION	TO	STATION	TREE REMOVAL, ACRES	PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	CURB REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	CONCRETE BARRIER REMOVAL	PAVED SHOULDER REMOVAL	PARKING LOT PAVEMENT REMOVAL	REMOVE IMPACT ATTENUATORS, NO SALVAGE	APPROACH SLAB REMOVAL	FENCE REMOVAL
				ACRE	SQ YD	SQ YD	FOOT	FOOT	SQ FT	FOOT	SQ YD	SQ YD	EACH	SQYD	FOOT
MORGAN STREET	3602+45	TO	3606+85	-	988	-	-	462	2850	-	-	-	-	296	-
MORGAN STREET - UIC DRIVEWAY	3602+88	TO	3603+20	-	-	61	26	-	-	-	-	61	-	-	-
MORGAN STREET - DRIVEWAY	3606+35	TO	3606+52	-	-	22	-	-	-	-	-	-	-	-	-
CONGRESS PARKWAY	3305+50	TO	3306+63	-	473	-	-	310	1069	-	-	-	-	-	134
MORGAN STREET EXIT RAMP	1002+56	TO	1005+92	-	229	-	-	562	-	-	18	-	1	-	-
I-290 WESTBOUND	338+11	TO	340+60	-	-	-	-	155	-	248	346	-	-	-	148
I-290 EASTBOUND	338+25	TO	339+86	0.06	-	-	-	-	-	229	116	-	-	-	-
TOTAL				0.06	1690	83	26	1489	3919	477	480	61	1	296	282
ROUNDED TOTAL				0.25	1690	83	26	1489	3919	477	480	61	1	296	282

FILE PATH = p:\388031\pmt\escomon\me\local\AECOM\01\Documents\01\Americas\Transportation\60269938_Circle\Phase_1\000_CAD\006_Roadway\Sheets\60W25_Contract\0160W25-sht-Schedule-01



DI60W25-sht-Schedule-01
USER NAME = chitua
PLOT SCALE = 50.0000' / in.
PLOT DATE = 6/13/2013

DESIGNED - AFC
DRAWN - AFC
CHECKED - DBM
DATE - 6/17/2013

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-007R	COOK	317	31
CONTRACT NO. 60W25			ILLINOIS FED. AID PROJECT	