

SCHEDULE OF QUANTITIES
IL 68 (DUNDEE RD) AT BARRINGTON MIDDLE SCHOOL ENTRANCE

		1 -	OU V DOINDEL NOT AT DANNINGTON MIDDLE SCHOOL LIVINGHOL
NO. QUA	ANT.	UNIT	
1.	1	EACH	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
2.	1	EACH	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET
3.	3	EACH	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED
4.	3	EACH	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED
5.	1	EACH	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED
6.	1	EACH	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED
7.	1	EACH	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED
8.	4	EACH	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM
9.	6	EACH	INDUCTIVE LOOP DETECTOR
10.	1	EACH	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT
11.	1	EACH	UNINTERRUPTABLE POWER SUPPLY, SPECIAL

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

4 EACH TRAFFIC SIGNAL BACKPLATE

TRAFF ELECTRI	TOTAL WATTAGE				
		WATTAGE			
TYPE	NO. LAMPS	INCAND.	L.E.D.	OPERATION	
SIGNAL (RED)	11	135	17	0.50	93.5
SIGNAL (YELLOW)	11	135	25	0.25	68.75
SIGNAL (GREEN)	11	135	15	0.25	41.25
ARROW	4	135	12	0.10	4.8
PED. SIGNAL	-	90	25	1.00	-
CONTROLLER	1	-	100	1.00	100.0
LUMINAIRE	-	-	250	0.50	-
L.E.D. ST. NAME SIGN	-	-	64	0.50	-
VIDEO SYSTEM	-	-	150	1.00	-
BATTERY BACKUP	1	-	25	1.00	25.0
ILLUMINATED SIGN	-	-	25	0.05	-
				TOTAL =	333.3

ENERGY COSTS - BILLED TO: <u>IL DEPT. OF TRANSPORTA</u>TION
(ADDRESS) <u>201 W. CENTER COURT</u>
(ADDRESS) <u>SCHAUMBURG, IL 60196-1</u>096

ENERGY SUPPLY - CONTACT: DAVE SCHACHT
PHONE: 630-437-2129

FILE NAME =

D160W38-019.dgn

COMPANY: COMED - OAKBROOK TERRACE

USER NAME = gwhitten

PLOT DATE = 5/7/2013

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "NTCIP" COMPLIANT.

KLB

05/10/13


DRAWN

DATE

CHECKED

NOTE: THE EXISTING CONTROLLER IS AN ECONOLITE ASC/2-2100 IN A TYPE IV CABINET. 1 NUMBER OF GROUND 8 ∀≯ CABLES AS PER PLAN MA_{II}| IL 68 <u>α</u> ≻ υ (DUNDEE RD) (1) RELOCATION OF THE EXISTING PHASING UNIT FOR THE EMERGENCY VEHICLE PRE-EMPTION SYSTEM SHALL BE INCLUDED IN THE COST OF THE PAY ITEM "FULL ACTUATED CONTROLLER AND CABINET OF THE TYPE

CABLE PLAN



DESIGNED - JRD REVISED GW3 REVISED

REVISED

REVISED

CONSTRUCTION NOTE:

SPECIFIED".

SCHEDULE OF QUANTITIES, CABLE PLAN, PHASE DESIGNATION DIAGRAM, & EMERGENCY VEHICLE PREEMPTION SEQUENCE IL 68 (DUNDEE RD) AT BARRINGTON MIDDLE SCHOOL ENTRANCE SHEETS STA. SHEET

GHA #4085.889 TOTAL SHEET NO. 62 19 SECTION COUNTY VAR 2013-007 TS COOK CONTRACT NO. 60W38

EACH CABINET AND CONTROLLER (COMPLETE) 6 EACH TRAFFIC SIGNAL HEAD, 1-FACE, 3-SECTION

EACH TRAFFIC SIGNAL HEAD, 1-FACE, 5-SECTION EACH TRAFFIC SIGNAL HEAD, 2-FACE, 3-SECTION

EACH TRAFFIC SIGNAL HEAD, 2-FACE, 1-3 SECTION, 1-5 SECTION

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**